APPENDIX I

UNITIZATION PROCEDURES FOR BOXED AMMUNITION AND COMPONENTS ON 4-WAY ENTRY PALLETS


CARTRIDGE, IO GAGE, BLANK, PACKED 500 PER WOODEN BOX, UNITIZED 40 BOXES PER 35" X 45½" PALLET; APPROX BOX SIZE 15½" L X 9½" W X 9½" H

PALLET UNIT DATA								
1TEMS IN	CLUDED	HA	WEIGHT					
NSN	DODIC	DOT CLASS	CG CLASS	QD CLASS	COMP GROUP	(LBS)		
1305-00- 028-5035	A010	С	I	1.4	s	1,552		

NOTICE: THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA1002.

	REVIS		MEK MIN					
				100 Je	C3-4			
			POWNER KANTO ANNAMENT BATERIE. READMESS COMMAND FOR BOTH KANTON COMMANDERS CERTIFICATION APPROVED BY DODGE OF COMMAND					
	17		U.S. ARMY DEPENDE AMOUNTHON CENTER AND SCHOOL					
			U. S. ARMY DARCOM DRAWING					
	7		APRIL 1980					
1 1			CLASS	DIVISION	DRAWING	FILE		
			19	48	4116/1	20PA 1002		

DO NOT SCALE



BILL OF MATERIAL PALLET, 35" X 45-1/2" --- 1 REQD STEEL STRAPPING, 3/4" --- 94.00' REQD SEAL FOR 3/4" STRAPPING 7 REQD 1 REQD 65 LBS -6.71 LBS 7 REQD

TOTAL WEIGHT ---

CUBE --

PALLET .


PAGE 2

GENERAL NOTES

- A. THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA1002. TO PRODUCE AN APPROVED UNIT LOAD, ALL PERTINENT PROCEDURES, SPECIFICATIONS AND CRITERIA SET FORTH WITHIN THE BASIC DRAWING WILL APPLY TO THE PROCEDURES DELINEATED IN THIS APPENDIX. ANY EXCEPTIONS TO THE BASIC PROCEDURES ARE SPECIFIED IN THIS APPENDIX.
- B. DIMENSIONS, CUBE AND WEIGHT OF A PALLET UNIT WILL VARY SLIGHTLY DEPEND-ING UPON THE ACTUAL DIMENSIONS OF THE BOXES AND THE WEIGHT OF THE SPECIFIC ITEM BEING UNITIZED.
- C. INSTALL EACH HORIZONTAL STRAP TO ENCIRCLE EACH LAYER OF BOXES ON THE PALLET. HORIZONTAL STRAP MUST BE TENSIONED AND SEALED PRIOR TO APPLICATION OF TIEDOWN STRAPS.
- D. INSTALL EACH TIEDOWN STRAP TO PASS UNDER THE DECK/STRINGER BOARDS OF THE PALLET AND TO BE LOCATED BETWEEN THE VERTICAL END CLEATS OF THE BOXES. TIEDOWN STRAPS WILL NOT BE APPLIED UNTIL THE HORIZONTAL STRAPS HAVE BEEN TENSIONED AND SEALED.
- E. THE FOLLOWING DARCOM DRAWINGS ARE APPLICABLE FOR OUTLOADING AND STORAGE OF THE ITEMS COVERED BY THIS APPENDIX.

CARLOADING ---------- DRAWING 19-48-4115-5PA1002
TRUCKLOADING ------- DRAWING 19-48-4117-11PA1003 ----- DRAWING 19-48-4118-1-2-14-22PA 1002

- F. FOR METHOD OF SECURING A STRAP CUTTER TO THE PALLET UNIT, SEE DARCOM DRAWING 19-48-4127-20P1000.
- G. IF ITEMS COVERED HEREIN ARE UNITIZED PRIOR TO ISSUANCE OF THIS APPENDIX, THE BOXES NEED NOT BE REUNITIZED SOLELY TO CONFORM TO THIS APPENDIX.
- H. THE UNITIZATION PROCEDURES DEPICTED HEREIN MAY ALSO BE USED FOR UNITIZING 10 GAGE CARRIDGES WHEN IDENTIFIED BY DIFFERENT NATIONAL STOCK NUMBERS (NSN) THAN WHAT IS SHOWN ON THE TITLE PAGE, PROVIDED THE BOX PACK DOES NOT VARY FROM WHAT IS DELINEATED HEREIN. THE EXPLOSIVE CLASSIFICATION OF OTHER ITEMS MAY BE DIFFERENT THAN WHAT IS SHOWN.



- 1,552 LBS (APPROX)

---- 38.9 CU FT (APPROX)