APPENDIX 120E

UNITIZATION PROCEDURES FOR BOXED AMMUNITION AND COMPONENTS ON 4-WAY ENTRY PALLETS


CHARGE, DEMOLITION, BLOCK, PACKED 16 PER WOODEN BOX, UNITIZED 48 BOXES PER 40" 48" PALLET; APPROX BOX SIZE $13\frac{1}{2}$ " L X 10" W X $10\frac{1}{4}$ " H

PALLET UNIT DATA							
ITEMS INCLUDED		HAZARD CLASSIFICATION				WEIGHT	
NSN	DODIC	DOT CLASS	CG CLASS	QD CLASS	COMP GROUP	(LBS)	
1375- 00-028-5136	M037	Α .	IX-B	1, 1	D	2, 200	

NOTICE: THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA1002.

REVIS	SIONS	XU	20	#/New		
		Rott/	2	Byrd	, y	
		1			AEADINEDS COMMAND	
		Jan 1	me Kul	TI DO	Tille	
		MATERIEL D	Y ORDER OF COL	MANONS SENERAL	U. S. ARMY	
		4		X. By a		
		U. S. ARMY DARCOM DRAWING				
		MAY 1980				
		CLASS	DIVISION	DRAWING	FILE	
		19	48	4116/ 120 E	20 PA	
		.9	+0	120 E	1002	

O NOT SCALE



GENERAL NOTES


- A. THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CON-JUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA1002. TO PRODUCE AN APPROVED UNIT LOAD, ALL PRITINENT PROCEDURES, SPECIFICATIONS AND CRITERIA SET FORTH WITHIN THE BASIC DRAWING WILL APPLY TO THE PROCEDURES DELINEATED IN THIS APPENDIX. ANY EXCEPTIONS TO THE BASIC PROCEDURES ARE SPECIFIED IN THIS APPENDIX.
- B. DIMENSIONS, CUBE AND WEIGHT OF A PALLET UNIT WILL VARY SLIGHTLY DEPENDING UPON THE ACTUAL DIMENSIONS OF THE BOXES AND THE WEIGHT OF THE SPECIFIC ITEM BEING UNITIZED.
- C. INSTALL EACH HORIZONTAL STRAP TO ENCIRCLE A LAYER OF BOXES ON THE PALLET. HORIZONTAL STRAPS MUST BE TENSIONED AND SEALED PRIOR TO APPLICATION OF TIEDOWN STRAPS.
- D. INSTALL EACH TIEDOWN STRAP TO PASS UNDER THE DECK/STRINGER BOARDS OF THE PALLET AND TO BE LOCATED AS SHOWN, TIEDOWN STRAPS WILL NOT BE APPLIED UNTIL THE HORIZONTAL STRAPS HAVE BEEN TENSIONED AND SEALED.
- E. THE FOLLOWING DARCOM DRAWINGS ARE APPLICABLE FOR OUTLOADING AND STORAGE OF THE ITEMS COVERED BY THIS APPENDIX.

CARLOADING	DRAWING 19-48-4115-5PA 1002
TRUCKLOADING	DRAWING 19-48-4117-11PA1003
ST ORAGE	DRAWING 19-48-4118-1-2-14-22PA 1002

- F. FOR METHOD OF SECURING A STRAP CUTTER TO THE PALLET UNIT, SEE DARCOM DRAWING 19-48-4127-20P1000.
- G. IF ITEMS COVERED HEREIN ARE UNITIZED PRIOR TO ISSUANCE OF THIS APPENDIX, THE BOXES NEED NOT BE REUNITIZED SOLELY TO CONFORM TO THIS APPENDIX.
- H. THE UNITIZATION PROCEDURES DEPICTED HEREIN MAY ALSO BE USED FOR UNITIZING DEMOLITION CHARGES WHEN IDENTIFIED BY DIFFERENT NATIONAL STOCK NUMBERS (NSN) THAN WHAT IS SHOWN ON THE TITLE PAGE, PROVIDED THE BOX PACK DOES NOT VARY FROM WHAT IS DELINEATED HEREIN. THE EXPLOSIVE CLASSIFICATION OF OTHER ITEMS MAY BE DIFFERENT THAN WHAT IS SHOWN.

BILL OF MATERIAL						
101.67	REQD		80 LBS 7.26 LBS NIL			
	1 01.67'	1 REQD	1 REQD			

48 BOXES OF DEMOLITION CHARGES (16 PER BOX)@ 44 LBS --



2,112 LBS (APPROX) 8 LBS 80 LBS

2,200 LBS (APPROX) 45,3 CU FT (APPROX)

PALLET -

TOTAL WEIGHT