APPENDIX 125B

UNITIZATION PROCEDURES FOR **BOXED AMMUNITION AND COMPO-NENTS ON 4-WAY ENTRY PALLETS**

DEMOLITION KIT, BANGALORE TORPEDO, 2.5 FT, M1A3, PACKED ONE PER WOODEN BOX, UNITIZED 20 BOXES PER 35" X 45-1/2" PALLET; APPROX BOX SIZE 35-3/4" L X 13-1/8" W X 7" H

NOTICE: THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA1002.

DISTRIBUTION STATEMENT A

APPROVED FOR PUBLIC RELEASE DISTRIBUTION IS UNLIMITED.

APPROVED, U.S. ARMY RESEARCH, DEVELOPMENT AND ENGINEERING COMMAND CAUTION: VERIFY PRIOR TO USE AT WWW.DAC.ARMY.MIL THAT THIS IS REHMSTEDT.MA Dopally signed by REHMSTED AMER. 1120548400 DN:-C-US, 0-US. Government, ou-DoD, Dap-RV. 0.0014. S. Government, ou-DoD, Dap-RV. 0.0014. S. Toleroment, 0-DoD, 0-DD, THE MOST CURRENT VERSION OF THIS DOCUMENT. THIS IS PAGE 1 OF 4. RDAR-EIL-TP DO NOT SCALE APPROVED, U.S. ARMY JOINT MUNITIONS COMMAND **APRIL 2005** CASILLAS.GILBE Digitally signed by CASILLAS.GILBERT.J.123 **ENGINEER** BASIC LAURA A. FIEFFER RT.J.1230393644 Ou=DoD, ou=PKI, ou=USA, Cn=CASILLAS, GILBERT.J.1230393 SPENCER HOVEY TECHNICIAN RF\/ AMS.JM-LIT **REVISION NO. 1 JANUARY 2014** TRANSPORTATION APPROVED BY ORDER OF COMMANDING FIEFFER.LAUR FIEFFER.LAURA.A.1230375727 **ENGINEERING** GENERAL, U.S ARMY MATERIEL COMMAND SEE THE REVISION LISTING ON PAGE 2 A.A.1230375727 ou=DoD, ou=PKI cn=FIEFFER.LAI DIVISON BARICKMAN. Digitally signed by BARICKMAN PHILIP W:123 On-chuls, chul S. Governm On-chuls, chi-BarickMan PHILIP W:123 Chi-BarickMa CLASS DIVISION DRAWING TESTED VALIDATION SHIMP.UPTON SHIM-UPTONR.1231257183 DN: e-US, e-US. Government. ou .R.1231257183 ou-PR.(0.e-USA, e-US. Government. ou .R.1231257183 ou-PR.(0.e-USA, ou-USA, ou-**ENGINEERING** DIVISON 0202202 4116/ 20PA1002 BEAVER.JERRY BEAVER.JERRY.W.12300 19 48 **ENGINEERING** 125B DIRECTORATE .W.1230949952 U.S. ARMY DEFENSE AMMUNITION CENTER

U.S. ARMY MATERIEL COMMAND DRAWING


PALLET UNIT DATA												
ITEMS INCL	UDED	*HAZARD		APPROX WEIGHT (LBS)								
NSN	DODIC	CLASS AND DIVISION	*COMPATI- BILITY GROUP									
1375- 01-528-7226	MP03	1. 1	D	1, 873								

^{*}HAZARD CLASSIFICATION DATA CONTAINED IN THE ABOVE CHART IS FOR GUIDANCE AND INFORMATIONAL PUR-POSES ONLY. VERIFICATION OF THE SPECIFIED DATA SHOULD BE MADE BY CONSULTING THE MOST RECENT JOINT HAZARD CLASSIFICATION SYSTEM LISTING OR OTHER APPROVED LISTING(S).

REVISION

REVISION NO. 1, DATED JANUARY 2014, CONSISTS OF:

- CHANGING DRAWING TITLE FROM 8 PER BOX TO 1 KIT PER BOX AND ADDING M1A3 TO NOMENCLATURE.
 ADDING A REFERENCE OF .029" THICK STRAPPING TO TIEDOWN AND LOAD STRAPS.
 CHANGING DRAWING REFERENCE IN NOTE "J" TO ARDEC DRAWING 13010551.



PALLET UNIT

SEE GENERAL NOTE "B" AT RIGHT.

20 BOXES DUNNAGE PALLET	 	 	 	 -	-	 -	-	-	-	-	-	8	LBS	(APPROX)
														(APPROX) (APPROX)

BILL OF MATERIAL

PALLET, 35" X 45-1/2" - - - - 1 REQD - - - - - - 65 LBS STEEL STRAPPING, 3/4" - 83.00' REQD - - - - - - 7.42 LBS SEAL FOR 3/4" STRAPPING - - - 6 REQD - - - - - NIL

GENERAL NOTES

- A. THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA1002. TO PRODUCE AN APPROVED UNIT LOAD, ALL PERTINENT PROCEDURES, SPECIFICATIONS AND CRITERIA SET FORTH WITHIN THE BASIC DRAWING WILL APPLY TO THE PROCEDURES DELINEATED IN THIS APPENDIX. ANY EXCEPTIONS TO THE BASIC PROCEDURES ARE SPECIFIED IN THIS APPENDIX
- B. DIMENSIONS, CUBE AND WEIGHT OF A PALLET UNIT WILL VARY SLIGHTLY DEPENDING UPON THE ACTUAL DIMENSIONS OF THE BOXES AND THE WEIGHT OF THE SPECIFIC ITEM BEING UNITIZED.
- C. THE LOAD STRAPS MAY BE THREADED THROUGH THE STRAP SLOTS OF A PALLET OR PRE-POSITIONED ON THE PALLET DECK PRIOR TO PLACING THE BOXES ON THE PALLET. LOAD STRAPS MUST BE TENSIONED AND SEALED PRIOR TO APPLICATION OF TIEDOWN STRAPS.
- D. INSTALL EACH TIEDOWN STRAP TO PASS UNDER THE DECK/STRINGER BOARDS OF THE PALLET AND TO BE LOCATED AS SHOWN. TIEDOWN STRAPS WILL NOT BE APPLIED UNTIL THE LOAD STRAPS HAVE BEEN TENSIONED AND SEALED.
- E. THE FOLLOWING AMC DRAWINGS ARE APPLICABLE FOR OUTLOADING AND STORAGE OF THE ITEMS COVERED BY THIS APPENDIX.

CARLOADI NG - - - 19-48-4115-5PA1002
TRUCKLOADI NG - - 19-48-4117-11PA1003
STORAGE - - - 19-48-4118-1-2-3-4-1422PA1002
END OPENI NG I SO
CONTAI NER - - - 19-48-4153-15PA1002
MI LVAN - - - - 19-48-4166-15PA1003
SI DE OPENI NG I SO
CONTAI NER - - - 19-48-4267-15PA1009

- F. IF ITEMS COVERED HEREIN ARE UNITIZED PRIOR TO ISSUANCE OF THIS REVISION TO THIS APPENDIX, THE BOXES NEED NOT BE REUNITIZED SOLELY TO CONFORM TO THIS REVISION.
- G. THE UNITIZATION PROCEDURES DEPICTED HEREIN MAY ALSO BE USED FOR UNITIZING BANGALORE TORPEDO DEMOLITION KITS WHEN IDENTIFIED BY DIFFERENT NATIONAL STOCK NUMBERS (NSN) THAN WHAT IS SHOWN ON PAGE 2, PROVIDED THE BOX PACK DOES NOT VARY FROM WHAT IS DELINEATED HEREIN. THE EXPLOSIVE CLASSIFICATION OF OTHER ITEMS MAY BE DIFFERENT THAN WHAT IS SHOWN.
- H. THE STYLE 1A PALLET DELINEATED IN THE DETAIL AT LEFT NEED NOT HAVE CHAMFERS OR STRAP SLOTS AS SPECIFIED WITHIN MILITARY SPECIFICATION MIL-DTL-15011 WHEN USED FOR THE UNITIZATION OF ITEMS COVERED BY THIS APPENDIX.
- J. FOR DETAILS OF THE MIL-DTL-2427 WOODEN BOX SEE ARDEC DRAWING 13010551.
- K. THE 52-1/2" WIDTH DIMENSION IS AN EXCEPTION TO THE BASIC PROCEDURES. HOWEVER, THE EXCEPTION IS NECESSARY FOR THE AMMUNITION PACK COVERED BY THIS APPENDIX TO MOST EFFECTIVELY GET AN ACCEPTABLE, COMPACT AND SOUND PALLET UNIT.

PAGE 3

