APPENDIX 127

UNITIZATION PROCEDURES FOR BOXED AMMUNITION AND COMPONENTS ON 4-WAY ENTRY PALLETS

CORD, DETONATING, REINFORCED, DUMMY, PACKED 6 SPOOLS PER WOODEN BOX, UNITIZED 12 BOXES PER 35" X 45-1/2" PALLET; APPROX BOX SIZE 23-1/2" L X 13-1/2" W X 13-1/2" H

NOTICE: THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA1002.

DISTRIBUTION STATEMENT A.

APPROVED FOR PUBLIC RELEASE;
DISTRIBUTION IS UNLIMITED.

U.S. ARMY MATERIEL COMMAND DRAWING APPROVED, U.S. ARMY ARMAMENT, MUNITIONS AND CHEMICAL COMMAND DRAFTSMAN BETTY J. KUNDERT SANDRA M. ENGINEER SCHULTZ SUPPLY ENGINEERING DIVISION VALIDATION ENGINEERING TRANSPORTATION ENGINEERING DIVISION SMCAR-ESK APPROVED BY ORDER OF COMMANDING GENERAL, U.S. ARMY MATERIEL COMMAND DECEMBER 1980 NOIZIVIO DRAWING FILE CLASS U.S. ARMY DEFENSE AMMUNITION CENTER AND SCHOOL REVISION NO. 1 AUGUST 1994 4116/ 20PA 19 48 127 1002 SEE THE REVISION LISTING ON PAGE 2

DO NOT SCALE


PALLET UNIT DATA				
ITEMS INCLUDED		HAZARD CLASS AND DIVISION •		ADDDOV
NZN	DODIC	OD CLASS	COMP GROUP	APPROX WEIGHT LBS
1375-	M458			1,331

HAZARD CLASSIFICATION DATA CONTAINED IN THE ABOVE CHART IS FOR GUIDANCE AND INFORMATIONAL PURPOSES ONLY. VERIFICATION OF THE SPECIFIED DATA SHOULD BE MADE BY CONSULTING THE MOST RECENT JOINT HAZARD CLASSIFICATION SYSTEM LISTING OR OTHER APPROVED LISTING(S).

REVISION

REVISION NO. 1, DATED AUGUST 1994, CONSISTS OF:

1. DELETING NSN FROM "PALLET UNIT DATA" CHART.



PALLET UNIT

SEE GENERAL NOTE "B" AT RIGHT.

TOTAL WEIGHT - - - - - - - - - - 1,331 LBS (APPROX)

CUBE - - - - - - 35.8 CU FT (APPROX)

BILL OF MATERIAL


PALLET, 35" X 45-1/2" - - - 1 REOD - - - - 65 LBS STEEL STRAPPING, 3/4" - 80.50' REOD - - - 5.75 LBS SEAL FOR 3/4" STRAPPING - - 6 REOD - - - - - NIL

GENERAL NOTES

- A. THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA1002. TO PRODUCE AN APPROVED UNIT LOAD, ALL PERTINENT PROCEDURES, SPECIFICATIONS AND CRITERIA SET FORTH WITHIN THE BASIC DRAWING WILL APPLY TO THE PROCEDURES DELINEATED IN THIS APPENDIX. ANY EXCEPTIONS TO THE BASIC PROCEDURES ARE SPECIFIED IN THIS APPENDIX.
- B. DIMENSIONS, CUBE AND WEIGHT OF A PALLET UNIT WILL VARY SLIGHTLY DEPENDING UPON THE ACTUAL DIMENSIONS OF THE BOXES AND THE WEIGHT OF THE SPECIFIC ITEM BEING UNITIZED.
- INSTALL EACH HORIZONTAL STRAP TO ENCIRCLE A LAYER OF BOXES ON THE PALLET. HORIZONTAL STRAPS MUST BE TENSIONED AND SEALED PRIOR TO THE APPLICATION OF TIEDOWN STRAPS.
- D. INSTALL EACH TIEDOWN STRAP TO PASS UNDER THE TOP DECK BOARDS OF THE PALLET AND TO BE LOCATED AS SHOWN. TIEDOWN STRAPS WILL NOT BE APPLIED UNTIL THE HORIZONTAL STRAPS HAVE BEEN TENSIONED AND SFAIFD.
- E. THE FOLLOWING AMC DRAWINGS ARE APPLICABLE FOR OUTLOADING AND STORAGE OF THE ITEMS COVERED BY THIS APPENDIX.

CARLOADING - - - 19-48-4115-5PA1002 TRUCKLOADING - - 19-48-4117-11PA1003 STORAGE - - - 19-48-4118-1-2-3-4-14-22PA1002 END OPENING ISO CONTAINER - - - 19-48-4153-15PA1002 MILVAN - - - - 19-48-4166-15PA1003 SIDE OPENING ISO CONTAINER - - - 19-48-4267-15PA1009

- F. FOR METHOD OF SECURING A STRAP CUTTER TO THE PALLET UNIT, SEE AMC DRAWING 19-48-4127-20P1000.
- G. IF ITEMS COVERED HEREIN ARE UNITIZED PRIOR TO ISSUANCE OF THIS APPENDIX, THE BOXES NEED NOT BE REUNITIZED SOLELY TO CONFORM TO THIS APPENDIX.
- H. THE UNITIZATION PROCEDURES DEPICTED HEREIN MAY ALSO BE USED FOR UNITIZING DETONATING CORD WHEN IDENTIFIED BY DIFFERENT NATIONAL STOCK NUMBERS (NSN) THAN WHAT IS SHOWN ON PAGE 2, PROVIDED THE BOX PACK DOES NOT VARY FROM WHAT IS DELINEATED HEREIN. THE EXPLOSIVE CLASSIFICATION OF OTHER ITEMS MAY BE DIFFERENT THAN WHAT IS SHOWN.
- J. THE STYLE 1A PALLET DELINEATED IN THE DETAIL AT LEFT NEED NOT HAVE CHAMFERS OR STRAP SLOTS AS SPECIFIED WITHIN MILITARY SPECIFICATION MIL-P-15011 WHEN USED FOR THE UNITIZATION OF ITEMS COVERED BY THIS APPENDIX.



FILLER ASSEMBLY

(FOR MINUS ONE BOX)