APPENDIX 131A

UNITIZATION PROCEDURES FOR BOXED AMMUNITION AND COMPONENTS ON 4-WAY ENTRY PALLETS


IGNITER, BLASTING TIME FUSE, PACKED 250 PER WOODEN BOX, UNITIZED 24 BOXES PER 35" X 45½" PALLET; APPROX BOX SIZE 22½" L X 11¾ W X 7½"H

PALLET UNIT DATA								
ITEMS INCLUDED		HAZ	WEIGHT					
NSN	DODIC	DOT CLASS	CG CLASS	QD CLASS	COMP GROUP	(LBS)		
1375- 00-028-5 20 0	M766	С	I	1. 4	S	1,270		

NOTICE: THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA1002.

REVISIONS		DRAFTSMAN	WR WR	FILM			
			GC6	40	GRG OFFICE		
			APPROVED. U. S. ARMY ARMAMENT MATERIEL READNESS COMMAND WHAT SEPTIMENT ONS IR J. TIMO ORS. IR J. TIMO				
	<u> </u>		APPROVED B	Y ORDER OF COMEVELOPMENT AND	MANDING GENERAL READINESS COMM	. U. S. ARMY AND (DARCOM)	
			U.S. ARMY DEFENSE AMMUNITION CENTER AND SCHOOL				
			U. S. ARMY DARCOM DRAWING				
				MAY	1982		
			CLASS	DIVISION	DRAWING	FILE	
			19	48	4116/	20PA	
					131A	1002	

DO NOT SCALE



GENERAL NOTES

- A. THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CON-JUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA1002. TO PRODUCE AN APPROVED UNIT LOAD, ALL PEXTINENT PROCEDURES, SPECIFICATIONS AND CRITERIA SET FORTH WITHIN THE BASIC DRAWING WILL APPLY TO THE PROCEDURES DELINEATED IN THIS APPENDIX, ANY EXCEPTIONS TO THE BASIS PROCEDURES ARE SPECIFIED IN THIS APPENDIX.
- B. DIMENSIONS, CUBE AND WEIGHT OF A PALLET UNIT WILL VARY SLIGHTLY DEPENDING UPON THE ACTUAL DIMENSIONS OF THE BOXES AND THE WEIGHT OF THE SPECIFIC ITEM BEING UNITIZED.
- C. THE LOAD STRAPS MAY BE THREADED THROUGH THE STRAP SLOTS OF A PALLET OR PRE-POSITIONED ON THE PALLET DECK PRIOR TO PLACING BOXES ON THE PALLET. LOAD STRAPS MUST NOT BE TENSIONED AND SEALED UNTIL TIEDOWN STRAPS NAVE BEEN TENSIONED AND SEALED.
- D. INSTALL EACH TIEDOWN STRAP TO PASS UNDER THE TOP DECK BOARDS OF THE PALLET AND TO BE LOCATED AS SHOWN.
- E. THE FOLLOWING DARCOM DRAWINGS ARE APPLICABLE FOR OUT-LOADING AND STORAGE OF THE ITEMS COVERED BY THIS APPENDIX.

CARLOADINGDRAWING	19-48-4115-5PA1002
TRUCKLOADING DRAWING	19-48-4117-11PA1003
STORAGE	19-48-4118-1-2-3-4-14-
	22PA 1002

- F. FOR METHOD OF SECURING A STRAP CUTTER TO THE PALLET UNIT, SEE DARCOM DRAWING 19-48-4127-20P1000.
- G. IF ITEMS COVERED HEREIN ARE UNITIZED PRIOR TO ISSUANCE OF THIS APPENDIX, THE BOXES NEED NOT BE REUNITIZED SOLELY TO CONFORM TO THIS APPENDIX.
- H. THE UNITIZATION PROCEDURES DEPICTED HEREIN MAY ALSO BE USED FOR UNITIZING IGNITERS WHEN IDENTIFIED BY DIFFERENT NATIONAL STOCK NUMBERS (NSN.) THAN WHAT IS SHOWN ON THE TITLE PAGE, PROVIDED THE BOX PACK DOES NOT VARY FROM WHAT IS DELINEATED HEREIN. THE EXPLOSIVE CLASSIFICATION. OF OTHER ITEMS MAY BE DIFFERENT THAN WHAT IS SHOWN.

