APPENDIX 146B

UNITIZATION PROCEDURES FOR BOXED AMMUNITION AND COMPONENTS ON 4-WAY ENTRY PALLETS


CUTTER, CARTRIDGE ACTUATED, M2, PACKED IOO PER WOODEN BOX, UNITIZED 32 BOXES PER 35" X 45½" PALLET; APPROX BOX SIZE I7½" L X I2¾" W X 9½" H

PALLET UNIT DATA									
ITEMS INCLUDED		HAZARD CLASSIFICATION				WEIGHT			
NSN	DODIC	DOT CLASS	CG CLASS	QD CLASS	COMP GROUP	(LBS)			
1377- 00-028-5412	M504	С	I	1. 4	S	1,768			

NOTICE: THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA1002.

REVISIONS			DRAFTSMAN		FILLUS		
			RSHT APPROVED, I	U. S. ARMY ARM	MENT BATERIEL R	EADINESS COMMAND	
	$-V_{-}$		Potes Charage - Elle.				
			DRSAR - MAI	0	DRSAR - TMD		
			APPROVED BY ORDER OF COMMANDING GENERAL, U. S. ARMY MATERIEL DEVELOPMENT AND READINESS COMMAND (DARCOM)				
			U.S. ARMY DEPENSE AMMANITION CENTER AND SCHOOL				
	V I		U. S. 7	ARMY D	ARCOM I	DRAWING	
			JULY 1980				
			CLASS	DIVISION	DRAWING	FILE	
			19	48	4116/	20PA	
					146B	1002	

DO NOT SCALE



SEE GENERAL NOTE "B" AT RIGHT.


32 BOXES OF CUTTER, CARTRIDGE ACTUATED (100 PER BOX) @ 53 LBS 1,696	
DUNNA GE 7	LBS
PALLET 65	LBS

TOTAL WEIGHT -----1,768 LBS (APPROX)
CUBE ------45.4 CU FT (APPROX)

BILL OF MATERIAL

PALLET, 35" X 45-1/2" ----- 1 REQD ------ 65 LBS
STEEL STRAPPING, 3/4" ---- 84.67 REQD ------- 6.05 LBS
SEAL FOR 3/4" STRAPPING --- 6 REQD ------ NIL

TIE PIECE, 1" X 4" X BOX HEIGHT (2 REQD). NAIL TO LONGITUDINAL PIECES W/2-6d NAILS AT EACH END



- STRAP BEARING PIECE, 2" X 4" X BOX HEIGHT MINUS 3" (AS REQD), NAIL TO VERTICAL PIECES W/2-10d NAILS AT EACH END. NOTE: WHEN A UNIT HAS MORE THAN EIGHT (8) BOXES OMITTED, THE FILLER ASSEMBLY OR ASSEMBLIES LOCATED IN AN OUTER STACK ON THE 35" SIDE OF THE PALLET WILL REQUIRE A "STRAP BEARING PIECE" UNDER THE HORIZONTAL STRAP. STAPLE STRAP TO "STRAP BEARING PIECE".

- LATERAL PIECE, 2" X 4" X BOX HEIGHT MINUS 3" (4 REQD), NAIL TO VERTICAL PIECES W/2-10d NAILS AT EACH END.

FILLER ASSEMBLY

(FOR MINUS ONE BOX)

PAGE 2

GENERAL NOTES

- A. THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CON-JUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA 1002. TO PRODUCE AN APPROVED UNIT LOAD, ALL PERTINENT PROCEDURES, SPECIFICATIONS AND CRITERIA SET FORTH WITHIN THE BASIC DRAWING WILL APPLY TO THE PROCEDURES DELINEATED IN THIS APPENDIX. ANY EXCEPTIONS TO THE BASIC PROCEDURES ARE SPECIFIED IN THIS APPENDIX
- B. DIMENSIONS, CUBE AND WEIGHT OF A PALLET UNIT WILL VARY SLIGHTLY DEPENDING UPON THE ACTUAL DIMENSIONS OF THE BOXES AND THE WEIGHT OF THE SPECIFIC ITEM BEING UNITIZED.
- C. INSTALL EACH HORIZONTAL STRAP TO ENCIRCLE A LAYER OF BOXES ON THE PALLET, HORIZONTAL STRAPS MUST BE TENSIONED AND SEALED PRIOR TO APPLICATION OF TIEDOWN STRAPS.
- D. INSTALL EACH TIEDOWN STRAP TO PASS UNDER THE DECK/STRINGER BOARDS OF THE PALLET AND TO BE LOCATED AS SHOWN. TIEDOWN STRAPS WILL NOT BE APPLIED UNTIL THE HORIZONTAL STRAPS HAVE BEEN TENSIONED AND SEALED.
- E. THE FOLLOWING DARCOM DRAWINGS ARE APPLICABLE FOR OUTLOADING AND STORAGE OF THE ITEMS COVERED BY THIS APPENDIX.

CARLOADING ------ DRAWING 19-48-4115-5PA 1002
TRUCKLOADING ------ DRAWING 19-48-4117-11PA 1003
STORA GE ----- DRAWING 19-48-4118-1-2-14-22PA 1002

- F. FOR METHOD OF SECURING A STRAP CUTTER TO THE PALLET UNIT, SEE DARCOM DRAWING 19-48-4127-20P1000.
- G. IF ITEMS COVERED HEREIN ARE UNITIZED PRIOR TO ISSUANCE OF THIS APPENDIX, THE BOXES NEED NOT BE REUNITIZED SOLELY TO CONFORM TO THIS APPENDIX.
- H. THE UNITIZATION PROCEDURES DEPICTED HEREIN MAY ALSO BE USED FOR UNITIZING CUTTERS, CARTRIDGE ACTUATED, WHEN IDENTIFIED BY DIFFERENT NATIONAL STOCK NUMBERS (NSN.) THAN WHAT IS SHOWN ON THE TITLE PAGE, PROVIDED THE BOX PACK DOES NOT VARY FROM WHAT IS DELINEATED HEREIN. THE EXPLOSIVE CLASSIFICATION OF OTHER ITEMS MAY BE DIFFERENT THAN WHAT IS SHOWN.