APPENDIX 14D

UNITIZATION PROCEDURES FOR BOXED AMMUNITION AND COMPONENTS ON 4-WAY ENTRY PALLETS

CARTRIDGE, CALIBER .50, PACKED 210 PER WIREBOUND BOX, UNITIZED 24 BOXES PER 40" X 48" PALLET; APPROX BOX SIZE $14\frac{1}{2}$ " L X $12\frac{3}{4}$ " W $8\frac{3}{8}$ " H


PALLET UNIT DATA										
ITEMS INCLUDED		HAZARD CLASSIFICATION				WEIGHT				
NSN	DODIC	DOT CLASS	CG CLASS	QD CLASS	COMP GROUP	(LBS)				
1305- 00-028-6487 00-028-6458 00-752-7638 00-028-6470 00-028-6490 00-028-6469	A587	C C C C C	I I I I I I	1. 4 1. 4 1. 4 1. 4 1. 4	G G G G	2,078 2,102 2,078 1,934 1,934 1,934				

NOTICE: THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA1002.

* SEE GENERAL NOTE "B" ON PAGE 2.

REVISIONS		net bus	/Mur		
	CHICKEN OF ESENCE OFFICE (STOCK OF THE COMMAND OF T				
	U. S. ARMY DARCOM DRAWING APRIL 1980				
	CLASS	DIVISION	DRAWING	FILE	
	19	48	4116/ 14D	20PA 1002	

DO NOT SCALE



ſ	BILL OF MATERIAL			
	PALLET, 40" X 48" 1 REQD	. 58	LBS	

GENERAL NOTES

- A. THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4-116-20PA 1002. TO PRODUCE AN APPROVED UNIT LOAD, ALL PERTINENT PROCEDURES, SPECIFICATIONS AND CRITERIA SET FORTH WITHIN THE BASIC DRAWING WILL APPLY TO THE PROCEDURES DELINEATED IN THIS APPENDIX. ANY EXCEPTIONS TO THE BASIC PROCEDURES ARE SPECIFIED IN THIS APPENDIX.
- B. DIMENSIONS, CUBE AND WEIGHT OF A PALLET UNIT WILL VARY SLIGHTLY DEPENDING UPON THE ACTUAL DIMENSIONS OF THE BOXES AND THE WEIGHT OF THE SPECIFIC ITEM BEING UNITIZED.
- C. INSTALL EACH HORIZONTAL STRAP TO ENCIRCLE A LAYER OF BOXES ON THE PALLET. NOTE THAT THE STRAPS WILL BE LOCATED AS DIMENSIONED, NEAR THE TOP OF EACH LAYER. HORIZONTAL STRAPS MUST BE TENSIONED AND SEALED PRIOR TO APPLICATION OF TIEDOWN STRAPS.
- D. INSTALL EACH TIEDOWN STRAP TO PASS UNDER THE TOP DECK BOARDS OF THE PALLET. NOTE THAT THE STRAPS WILL BE LOCATED AS DIMENSIONED NEAR THE SIDE CLEATS OF THE END PANELS OF THE BOX. TIEDOWN STRAPS WILL NOT BE APPLIED UNTIL THE HORIZONTAL STRAPS HAVE BEEN TENSIONED AND SEALED.
- E. THE FOLLOWING DARCOM DRAWINGS ARE APPLICABLE FOR OUTLOADING AND STORAGE OF THE ITEMS COVERED BY THIS APPENDIX.

- F. FOR METHOD OF SECURING A STRAP CUTTER TO THE PALLET UNIT, SEE DARCOM DRAWING 19-48-4127-20 P1000.
- G. IF ITEMS COVERED HEREIN ARE UNITIZED PRIOR TO ISSUANCE OF THIS APPENDIX, THE BOXES NEED NOT BE REUNITIZED SOLELY TO CONFORM TO THIS APPENDIX.
- H. THE UNITIZATION PROCEDURES DEPICTED HEREIN MAY ALSO BE USED FOR UNITIZING .50 CALIBER CARTRIDGES WHEN IDENTIFIED BY DIFFERENT NATIONAL STOCK NUMBERS (NSN) THAN WHAT IS SHOWN ON THE TITLE PAGE, PROVIDED THE BOX PACK DOES NOT VARY FROM WHAT IS DELINEATED HEREIN. THE EXPLOSIVE CLASSIFICATION OF OTHER ITEMS MAY BE DIFFERENT THAN WHAT IS SHOWN,
- J. POSITION THE THREE OUTBOARD BOXES OF THE BOTTOM LAYER ON THE 40" SIDE OF THE PALLET WITH THE TOP DOWNWARD, AND THE THREE OUTBOARD BOXES OF THE TOP LAYER ON THE 40" SIDE OF THE PALLET WITH THE TOP UPWARD.

