# APPENDIX 162A

# UNITIZATION PROCEDURES FOR BOXED AMMUNITION AND COMPONENTS ON 4-WAY ENTRY PALLETS

AGENT, DECONTAMINATING, DS2, PACKED IN 5-GAL PAIL, UNITIZED 24 PAILS PER 35" X 45-1/2" PALLET; PAIL SIZE 11-3/8" DIA X 13-1/2" H

NOTICE: THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA1002.

U.S. ARMY MATERIEL COMMAND DRAWING							
APPROVED, U.S. ARMY ARMAMENT, MUNITIONS AND	DRAFTSMAN		D. WHITMORE				
CHEMICAL COMMAND	ENGINEER		SANDRA M. SCHULTZ				
David Q. Richoul Stackwick	SUPPLY ENG DIVIS		TRANSPORTATION ENGINEERING DIVISION	VALIDATION ENGINEERING DIVISION			
SMCAR-ESK AMSMC-TMD	WFE	st	Demons	Amelitech			
APPROVED BY ORDER OF COMMANDING GENERAL, U.S. ARMY MATERIEL COMMAND	William of Ernst						
John L. Synd	E8el TZUDUA						
U.S. ARMY DEFENSE AMMUNITION CENTER AND SCHOOL	CLASS	NOIZIVID	DRAWING	FILE			
REVISION NO. 1 MARCH 1992	19	48	4116/	20PA			
SEE THE REVISION LISTING ON PAGE 2	.5	'0	162A	1002			

DO NOT SCAFE


PALLET UNIT DATA							
ITEMS INCL	.UDED	HAZARD CLASSIF		ATION •			
	NSN DODIC	CG CLASS	HAZARD CLASS AND DIVISION		APPROX WEIGHT		
NZN			0D CLASS	COMP GROUP	LBS		
6850- 00-753-4870			CORRO	SIVE	1,256		

 HAZARD CLASSIFICATION DATA CONTAINED IN THE ABOVE CHART IS FOR GUIDANCE AND INFORMATIONAL PURPOSES ONLY. VERIFICATION OF THE SPECIFIED DATA SHOULD BE MADE BY CONSULTING THE MOST RECENT HAZARDOUS COMPONENT SAFETY DATA STATEMENT 20059 OR THE APPROVED PACKAGING DRAWING.

### REVISION

REVISION NO. 1, DATED MARCH 1992, CONSISTS OF:

- 1. ADDING INTERMEDIATE DUNNAGE ASSEMBLY.
- 2. ADDING LOAD STRAPS.
- 3. UPDATING NOTES AND WEIGHTS.



SEE GENERAL NOTE "B" AT RIGHT.

24 PAILS OF DECONTAMINATING AGENT (5 GAL PAIL) @ 46 LBS - 1,104 LBS (APPROX) **PALLET** 65 LBS

> TOTAL WEIGHT - - - - - - - - - - - - 1,256 LBS (APPROX) ---- 33.67 CU FT (APPROX)

BILL OF MATERIAL					
LUMBER	LINEAR FEET	BOARD FEET			
1" X 4" 1" X 6"	27.04 60.52	9.01 30.26			
NAILS	NO. REOD	POUNDS			
6d (2")	130	0.76			
PALLET, 35" X 45-1/2" 1 REOD 65 LBS SIEEL STRAPPING, 3/4" - 107.90", REOD 7.68 LBS					

SEAL FOR 3/4" - 107.90 REOD - - - - NIL STAPLE, 15/16" X 3/4" - - 22 REOD - - - - NIL

SUPPORT PIECE, 2" X 4" X 6-3/4" LONGITUDINAL PIECE, 2" X 4" X 9-3/4" (4 REQD). NAIL TO THE LATERAL PIECES W/2-10d NAILS (2 REOD). AT EACH END. LATERAL PIECE, 2" X 4" X 6-3/4" (4 REDD). NAIL TO SUPPORT PIECE W/2-10d NAILS. 11-1/4 W/2-6d NAILS AT EACH JOINT. FILLER PIECE. -VERTICAL PIECE, 2" X 4" X CONTAINER HEIGHT (4 REOD). 2" X 4" X 6" (4 REQD). FILLER ASSEMBLY

(FOR MINUS ONE CONTAINER)


GENERAL NOTES

- THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA1002. TO PRODUCE AN APPROVED UNIT LOAD, ALL PERTINENT PROCEDURES, SPECIFICATIONS AND CRITERIA SET FORTH WITHIN THE BASIC DRAWING WILL APPLY TO THE PROCEDURES DELINEATED IN THIS APPENDIX. ANY EXCEPTIONS TO DELINEATED IN THIS APPENDIX. ANY EXCEPTIONS TO THE BASIC PROCEDURES ARE SPECIFIED IN THIS APPENDIX.
- DIMENSIONS, CUBE AND WEIGHT OF A PALLET UNIT WILL VARY SLIGHTLY DEPENDING UPON THE ACTUAL DIMENSIONS OF THE PAILS AND THE WEIGHT OF THE SPECIFIC ITEM BEING UNITIZED
- INSTALL EACH HORIZONTAL STRAP TO ENCIRCLE A DUNNAGE ASSEMBLY. HORIZONTAL STRAPS MUST BE TENSIONED AND SEALED PRIOR TO THE APPLICATION OF TIEDOWN AND LOAD
- INSTALL EACH TIEDOWN STRAP TO PASS UNDER THE TOP DECK BOARDS OF THE PALLET. NOTE THAT THE STRAPS WILL BE LOCATED AS SHOWN. TIEDOWN STRAPS WILL NOT BE APPLIED UNTIL THE HORIZONTAL AND LOAD STRAPS HAVE BEEN TENSIONED AND SEALED.
- THE FOLLOWING AMC DRAWINGS ARE APPLICABLE FOR OUTLOADING AND STORAGE OF THE ITEMS COVERED BY THIS APPENDIX.


CARLOADING - - - 19-48-4115-5PA1002 TRUCKLOADING - - 19-48-4117-11PA1003 STORAGE - - - - 19-48-4118-1-2-3-4-14-22PA1002 COMMERCIAL CONTAINER - - - - 19-48-4153-15PA1002 MILVAN - - - - 19-48-4166-15PA1003

- FOR METHOD OF SECURING A STRAP CUTTER TO THE PALLET UNIT, SEE AMC DRAWING 19-48-4127-20P1000.
- IF ITEMS COVERED HEREIN ARE UNITIZED PRIOR TO ISSUANCE OF THIS APPENDIX, THE PAILS NEED NOT BE REUNITIZED SOLELY TO CONFORM TO THIS APPENDIX.
- THE UNITIZATION PROCEDURES DEPICTED HEREIN MAY ALSO BE USED FOR UNITIZING DECONTAMINATING AGENT WHEN DE USED FOR UNITIZING DECUNIAMINATING AGENT WHEN IDENTIFIED BY DIFFERENT NATIONAL STOCK NUMBERS (NSN) THAN WHAT IS SHOWN ON PAGE 2, PROVIDED THE PAIL DOES NOT VARY FROM WHAT IS DELINEATED HEREIN. THE HAZARO CLASSIFICATION OF OTHER ITEMS MAY BE DIFFERENT THAN WHAT IS SHOWN
  - NOTICE: THE PAILS MUST BE ORIENTED IN SUCH A MANNER THAT AT LEAST ONE PRECAUTIONARY HANDLING LABLE AFFIXED TO A PAIL IS VISIBLE FROM EACH OF THE FOUR SIDES OF THE UNIT LOAD.
- THE STYLE 1A PALLET DELINEATED IN THE DETAIL AT LEFT NEED NOT HAVE CHAMFERS OR STRAP SLOTS AS SPECIFIED WITHIN MILITARY SPECIFICATION MIL-P-15011 WHEN USED FOR THE UNITIZATION OF ITEMS COVERED BY THIS APPENDIX.

PAGE 3



## (1 REOD)



## BOTTOM AND INTERMEDIATE ASSEMBLY

(1 EACH REOD)