APPENDIX 28P

UNITIZATION PROCEDURES FOR BOXED AMMUNITION AND COMPONENTS ON 4-WAY ENTRY PALLETS

CARTRIDGE, 60MM, ILLUMINATING, PACKED 16 PER WIREBOUND BOX, UNITIZED 24 BOXES PER 40" X 48" PALLET; APPROX BOX SIZE 15" L X 13-1/4" W X 20-1/4" H

NOTICE: THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA1002.

DISTRIBUTION STATEMENT A.								
APPROVED FOR PUBLIC RELEASE: DISTRIBUTION IS UNLIMITED.	U.S. ARMY MATERIEL COMMAND DRAWING							
	APPROVED, U.S. ARMY IN	DUSTRIAL	OPERATIONS	DRAF	NAMZT	BETTY	J. KUNDERT	
	Mard M. Ferland Lingther Ins		ENGINEER		SANDRA M. SCHULTZ			
			other Inc	SUPPLY ENGINEERING DIVISION		TRANSPORTATION VALIDATION ENGINEERING ENGINEERING DIVISION DIVISION	ENGINEERING	
	AMSTA-AR-ESK	OIZMA		J. J. Mic	hele u	J. French	- SHKsohn	
	APPROVED BY ORDER OF COMMANDING GENERAL, U.S. ARMY MATERIEL COMMAND			COGISTICS ENGINEERING OFFICE				
	Tany 1.		Intleed		FEE	BRUARY 1988		
	U.S. ARMY DEFENSE	E AMMUNIT	ION CENTER	ELASS	DIVIZION	DRAWING	FILE	
DO NOT SCALE	REVISION NO. 1	MAI	RCH 1997	19	48	4116/	20PA	
	SEE THE REVISION	LISTIN	NG ON PAGE 2	10	70	28P	1002	

PALLET UNIT DATA									
ITEMS INCL	.UDED	HAZARD AND DIV	APPROV						
NZN	DODIC	OD CLASS	COMP GROUP	APPROX WEIGHT LBS					
1310- 01-258-8689 01-438-6964	B647 BA04	(08)1.2 (08)1.2	0 0	2,872 2,872					


[■] HAZARD CLASSIFICATION DATA CONTAINED IN THE ABOVE CHART IS FOR GUIDANCE AND INFORMATIONAL PURPOSES ONLY. VERIFICATION OF THE SPECIFIED DATA SHOULD BE MADE BY CONSULTING THE MOST RECENT JOINT HAZARD CLASSIFICATION SYSTEM LISTING OR OTHER APPROVED LISTING(S).

REVISIONS

REVISION NO. 1, DATED MARCH 1997, CONSISTS OF:

- ADDING ITEM BY NATIONAL STOCK NUMBER TO "PALLET UNIT DATA" CHART.
- 2. CHANGING THE WEIGHT OF THE ITEM.
- 3. DELETING GENERAL NOTE RELATING TO STRAP CUTTER AND RE-LETTERING OTHER GENERAL NOTES.

PAGE 2



PALLET UNIT

SEE GENERAL NOTE "B" AT RIGHT.

TOTAL WEIGHT - - - - - - - - - - - 2,872 LBS (APPROX)
CUBE - - - - - - - - - - - 62.7 CU FT (APPROX)

GENERAL NOTES

- A. THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA1002. TO PRODUCE AN APPROVED UNIT LOAD, ALL PERTINENT PROCEDURES, SPECIFICATIONS AND CRITERIA SET FORTH WITHIN THE BASIC DRAWING WILL APPLY TO THE PROCEDURES DELINEATED IN THIS APPENDIX. ANY EXCEPTIONS TO THE BASIC PROCEDURES ARE SPECIFIED IN THIS APPENDIX.
- B. DIMENSIONS, CUBE AND WEIGHT OF A PALLET UNIT WILL VARY SLIGHTLY DEPENDING UPON THE ACTUAL DIMENSIONS OF THE BOXES AND THE WEIGHT OF THE SPECIFIC ITEM BEING UNITIZED.
- C. INSTALL EACH HORIZONTAL STRAP TO ENCIRCLE A LAYER OF BOXES ON THE PALLET. NOTE THAT THE STRAPS WILL BE LOCATED AS SHOWN. HORIZONTAL STRAPS MUST BE TENSIONED AND SEALED PRIOR TO THE APPLICATION OF TIEDOWN STRAPS.
- D. INSTALL EACH TIEDDWN STRAP TO PASS UNDER THE TOP DECK BOARDS OF THE PALLET. NOTE THAT THE STRAPS WILL BE LOCATED AS SHOWN, NEAR THE SIDE CLEATS OF THE END PANELS OF THE BOX. TIEDDWN STRAPS WILL NOT BE APPLIED UNTIL THE HORIZONTAL STRAPS HAVE BEEN TENSIONED AND SEALED.
- E. THE FOLLOWING AMC DRAWINGS ARE APPLICABLE FOR OUTLOADING AND STORAGE OF THE ITEMS COVERED BY THIS APPENDIX.

CARLOADING - - - 19-48-4115-5PA1002 TRUCKLOADING - - 19-48-4117-11PA1003 STORAGE - - - 19-48-4118-1-2-3-4-14-22PA1002 END OPENING ISO CONTAINER - - 19-48-4153-15PA1002 MILVAN - - - 19-48-4166-15PA1003 SIDE OPENING ISO


F. IF ITEMS COVERED HEREIN ARE UNITIZED PRIOR TO ISSUANCE OF THIS APPENDIX, THE BOXES NEED NOT BE REUNITIZED SOLELY TO CONFORM TO THIS APPENDIX.

CONTAINER - - - - 19-48-4267-15PA1009

- G. THE UNITIZATION PROCEDURES DEPICTED HEREIN MAY ALSO BE USED FOR UNITIZING SOMM CARTRIDGES WHEN IDENTIFIED BY DIFFERENT NATIONAL STOCK NUMBERS (NSN) THAN WHAT IS SHOWN ON PAGE 2, PROVIDED THE BOX PACK DOES NOT VARY FROM WHAT IS DELINEATED HEREIN. THE EXPLOSIVE CLASSIFICATION OF OTHER ITEMS MAY BE DIFFERENT THAN WHAT IS SHOWN.
- H. WHEN THE UNIT LOAD DEPICTED AT LEFT IS TO BE USED FOR UNITIZING MARINE CORPS AMMUNITION, ONE LAYER OF BOXES MUST BE OMITTED, TIEDOWN STRAP LENGTHS MUST BE DECREASED TO 12'-10", AND ONE HORIZONTAL STRAP MUST BE OMITTED. THIS WILL RESULT IN AN OVERALL UNIT HEIGHT OF 35-1/2", A GROSS UNIT WEIGHT OF 1,895 POUNDS, AND A UNIT CUBE OF 44.1 CUBIC FEET. ADDITIONALLY, THE UNIT MAY BE MODIFIED AS DESCRIBED WHEN BEING SHIPPED BY MILVAN OR ISO INTERMODAL FREIGHT CONTAINER. THE DETERMINATION TO REDUCE THE LOAD BY A LAYER FOR TRANSPORTATION WILL BE MADE BY THE RESPONSIBLE COMMAND AND WILL BE BASED UPON ECONOMICS OF TRANSPORTATION AND HANDLING.
- J. THE STYLE I PALLET DELINEATED IN THE DETAIL AT LEFT NEED NOT HAVE CHAMFERS OR STRAP SLOTS AS SPECIFIED WITHIN MILITARY SPECIFICATION MIL-P-15011 WHEN USED FOR THE UNITIZATION OF ITEMS COVERED BY THIS APPENDIX.

BILL OF MATERIAL

PALLET, 40" X 48" - - - - - - 1 REOD - - - 80 LBS STEEL STRAPPING, 3/4" - 1111.08' REOD - - 7.93 LBS SEAL FOR 3/4" STRAPPING - - - 7 REOD - - - NIL



FILLER ASSEMBLY

(FOR MINUS ONE BOX)

PAGE 4