APPENDIX 44B

UNITIZATION PROCEDURES FOR BOXED AMMUNITION AND COMPONENTS ON 4-WAY ENTRY PALLETS


CARTRIDGE, 90 MM, BLANK, PACKED 8 PER WOODEN BOX, UNITIZED 18 BOXES PER 35" \times 45½" PALLET; APPROX BOX SIZE $25\frac{3}{4}$ " L X 13" W $10\frac{1}{4}$ " H

PALLET UNIT DATA						
ITEMS INCLUDED		HAZARD CLASSIFICATION				WEIGHT
NSN	DODIC	DOT CLASS	CG CLASS	QD CLASS	COMP GROUP	(LBS)
1315- 00-542-1639 00-678-9911	C261 C261	B B	II-B II-B	1.3 1.3	C	1,980 1,980

NOTICE: THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA1002.

REVISIONS		DBAETSMAN CHECKER	nous 203	HERG OFFICE				
	\Box		RSHr/	De h	Synf	READINESS COMMAND		
-	+		- Jana DRSAR-HAD	fancene Kueter DC Teller				
			MATERIEL DE	APPROVED BY ORDER OF COMMANDING SEMERAL, U.S. ARMY MATERIEL DEVELOPMENT AND READINESS COMMAND (DARCOM)				
	1/-		7	U. S. ARMY DEF	ENSE AMMUNITION C	NTER AND SCHOOL		
	+		U. S. ARMY DARCOM DRAWING JUNE 1980					
			CLASS	DIVISION	DRAWING	FILE		
			19	48	4116/448	20PA 1002		

DO NOT SCALE




PALLET UNIT

SEE GENERAL NOTE "B" AT RIGHT.

DUNNAGE	TRIDGE (8 PER BOX)@ 106 LBS	7 LBS
		1,980 LBS (APPROX) 42.1 CU FT (APPROX)

BILL OF MATERIAL				
PALLET, 35" X 45-1/2" STEEL STRAPPING, 3/4"	95.50	REQ D 6.82 LBS		



GENERAL NOTES

- A. THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CON-JUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA 1002. TO PRODUCE AN APPROVED UNIT LOAD, ALL PERTINENT PROCEDURES, SPECIFICATIONS AND CRITERIA SET FORTH WITHIN THE BASIC DRAWING WILL APPLY TO THE PROCEDURES DELINEATED IN THIS APPENDIX. ANY EXCEPTIONS TO THE BASIC PROCEDURES ARE SPECIFIED IN THIS APPENDIX.
- B. DIMENSIONS, CUBE AND WEIGHT OF A PALLET UNIT WILL VARY SLIGHTLY DEPENDING UPON THE ACTUAL DIMENSIONS OF THE BOXES AND THE WEIGHT OF THE SPECIFIC ITEM BEING UNITIZED.
- C. THE LOAD STRAPS MAY BE INSTALLED THROUGH THE STRAP SLOTS OF A PALLET OR PRE-POSITIONED ON THE PALLET DECK PRIOR TO PLACING BOXES ON THE PALLET.
- D. INSTALL EACH TIEDOWN STRAP TO PASS UNDER THE DECK/STRINGER BOARDS OF THE PALLET AND TO BE LOCATED AS SHOWN. TIEDOWN STRAPS WILL BE TENSIONED AND SEALED PRIOR TO LOAD STRAPS.
- E. THE FOLLOWING DARCOM DRAWINGS ARE APPLICABLE FOR OUTLOADING AND STORAGE OF THE ITEMS COVERED BY THIS APPENDIX.

- F. FOR METHOD OF SECURING A STRAP CUTTER TO THE PALLET UNIT, SEE DARCOM DRAWING 19-48-4127-20P1000.
- G. IF ITEMS COVERED HEREIN ARE UNITIZED PRIOR TO ISSUANCE OF THIS APPENDIX, THE BOXES NEED NOT BE REUNITIZED SOLELY TO CONFORM TO THIS APPENDIX.
- H. THE UNITIZATION PROCEDURES DEPICTED HEREIN MAY ALSO BE USED FOR UNITIZING 90MM CARTRIDGES WHEN IDENTIFIED BY DIFFERENT NATIONAL STOCK NUMBERS (NSN) THAN WHAT IS SHOWN ON THE TITLE PAGE, PROVIDED THE BOX PACK DOES NOT VARY FROM WHAT IS DELINEATED HEREIN. THE EXPLOSIVE CLASSIFICATION OF OTHER ITEMS MAY BE DIFFERENT THAN WHAT IS SHOWN.