APPENDIX 65K

UNITIZATION PROCEDURES FOR BOXED AMMUNITION AND COMPONENTS ON 4-WAY ENTRY PALLETS


GRENADE, HAND, PACKED 40 PER WOODEN BOX, UNITIZED 27 BOXES PER 40" X 48" PALLET; APPROX BOX SIZE 18½" L X 13½" W X 13" H

PALLET UNIT DATA									
ITEMS INCLUDED		HAZ	WEIGHT						
NSN	DODIC	DOT CLASS	CG CLASS	QD CLASS	COMP GROUP	(LBS)			
1330- 00-028-5840	G890	A	IX	(08)1.1	F	2, 382			

NOTICE: THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA1002.

REVI		pt WA	Ffind				
		CHECKER LOG ENGAG OFFICE APPROVED US ARMY ARMAMENT MATERIEL READINESS COMMANO BYLL LAR FLOATING					
		DRSAR - LEP DRSAR - TMD APPROVED BY ORDER OF COMMANDING GENERAL, U. S. ARMY MATERIEL DEVELOPMENT AND REAGINESS COMMAND (DARCOM)					
		US ARMY DEFENSE AMMUNITION CENTER AND SCHOOL					
		U. S. ARMY DARCOM DRAWING APRIL 1982					
		CLASS	DIVISION	DRAWING	FILE		
		19	48	4116/ 65K	20PA 1002		

DO NOT SCALE



GENERAL NOTES

- A. THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CON-JUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA1002. TO PRODUCE AN APPROVED UNIT LOAD, ALL PER-TINENT PROCEDURES, SPECIFICATIONS AND CRITERIA SET FORTH WITHIN THE BASIC DRAWING WILL APPLY TO THE PROCEDURES DELINEATED IN THIS APPENDIX.
- B. DIMENSIONS, CUBE AND WEIGHT OF A PALLET UNIT WILL VARY SLIGHTLY DEPENDING UPON THE ACTUAL DIMENSIONS OF THE BOXES AND THE WEIGHT OF THE SPECIFIC ITEM BEING UNITIZED.
- C. THE LOAD STRAPS MUST BE PRE-POSITIONED ON THE PALLET DECK PRIOR TO PLACING BOXES ON THE PALLET. LOAD STRAPS MUST NOT BE TENSIONED AND SEALED UNTIL TIEDOWN STRAPS HAVE BEEN TEN-SIONED AND SEALED.
- D. INSTALL EACH TIEDOWN STRAP TO PASS UNDER THE TOP DECK BOARDS OF THE PALLET AND TO BE LOCATED AS SHOWN.
- E. THE FOLLOWING DARCOM DRAWINGS ARE APPLICABLE FOR OUTLOADING AND STORAGE OF THE ITEMS COVERED BY THIS APPENDIX.

CARLOADING ------ DRAWING 19-48-4115-5PA 1002
TRUCKLOADING ----- DRAWING 19-48-4117-11PA 1003
STORAGE ----- DRAWING 19-48-4118-1-2-3-4-14-22PA 1002

- F. FOR METHOD OF SECURING A STRAP CUTTER TO THE PALLET UNIT, SEE DARCOM DRAWING 19-48-4127-20P1000.
- G. IF ITEMS COVERED HEREIN ARE UNITIZED PRIOR TO ISSUANCE OF THIS APPENDIX, THE BOXES NEED NOT BE REUNITIZED SOLELY TO CONFORM TO THIS APPENDIX.
- H. THE UNITIZATION PROCEDURES DEPICTED HEREIN MAY ALSO BE USED FOR UNITIZING HAND GRENADES WHEN IDENTIFIED BY DIFFERENT NATIONAL STOCK NUMBERS (NSN.) THAN WHAT IS SHOWN ON THE TITLE PAGE, PROVIDED THE BOX PACK DOES NOT VARY FROM WHAT IS DELINEATED HEREIN. THE EXPLOSIVE CLASSIFICATION OF OTHER ITEMS MAY BE DIFFERENT THAN WHAT IS SHOWN.

SEE GENERAL NOTE "B" AT RIGHT.

----- 2,295 LBS (APPROX)

-- 80 LBS - 2,382 LBS (APPROX)

----- 59.5 CU FT (APPROX)

TIE PIECE, 1" X 4" X BOX WIDTH (2 REQD). NAIL TO LONGITUDINAL PIECES W/2-6d NAILS AT EACH END AND TO LATERAL PIECE W/1-

27 BOXES OF HAND GRENADES (40 PER BOX) @ 85 LBS -----

CURF -

DUNNAGE --PALLET ----

