## APPENDIX 65P

## UNITIZATION PROCEDURES FOR BOXED AMMUNITION AND COMPONENTS ON 4-WAY ENTRY PALLETS

GRENADE, HAND, FRAGMENTATION, PACKED 30 PER WOODEN BOX, UNITIZED 24 BOXES PER 35" X 45½" PALLET; APPROX BOX SIZE 18½" L X 11¼" W X II¼" H

PALLET UNIT DATA							
ITEMS	INCLUDED	HAZARD CLASSIFICATION®				WEIGHT	
NSN	DODIC	DOT CLASS	CG CLASS	QD CLASS	COMP GROUP	(LBS)	
1330- 00-133-8244 01-188-6024	G881 G883	A A	IV IV	(04) 1, 1 (04) 1, 1	F	1, 307 1, 331	

## **REVISIONS**

REVISION NO. 1, DATED JUNE 1984, CONSISTS OF:

- ADDING ITEM BY NATIONAL STOCK NUMBER TO "PALLET UNIT DATA" CHART.
- 2. ADDING SUPERSESSION NOTE.

REVISION NO. 2, DATED DECEMBER 1984, CONSISTS OF:

ADDING ITEM BY NATIONAL STOCK NUMBER TO "PALLET UNIT DATA" CHART.

REVISION NO. 3. DATED MAY 1989, CONSISTS OF:

- 1. CHANGING BOX POSITION ON PALLET.
- 2. UPDATING PALLET UNIT TO CONFORM TO ABOVE.
- 3. DELETING NSN FROM "PALLET UNIT DATA" CHART.
- 4. ADDING GENERAL NOTE "J".


NOTICE: THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA1002

• HAZARD CLASSIFICATION DATA CONTAINED IN THE ABOVE CHART IS FOR GUIDANCE AND INFORMATIONAL PURPOSES ONLY. VERIFICATION OF THE SPECIFIED DATA SHOULD BE MADE BY CONSULTING THE MOST RECENT JOINT HAZARD CLASSIFICATION SYSTEM LISTING OR OTHER APPROVED LISTING(S).

THIS DRAWING SUPERSEDES DRAWING 19-48-4116/65C-20PA1002, REVISION NO. 1, DATED MAY 1981.

REVISIONS & bh	e Alw			
DARLOCALD (R) (Supple-Record)	to Ernet			
William & Emet	in Albert and			
APPROVED BY ORDER OF C	DRIBMG - TIMD OMMANDING GENERAL, U. S. ARMY ND READINESS COMMAND (DARCOM)			
3 MAY 89 12 SECAL SER ABBILT TO U.S. ARMY DEFENSE	U.S. ARMY DEFENSE AMMUNITION CENTER AND SCHOOL			
Willia FErnst U.S. ARMY C	ARCOM DRAWING			
FEBR	FEBRUARY 1984			
CLASS DIVISION	DRAWING FILE			
10 40	4116/ 20PA			
19 48	65P 1002			

**DO NOT SCALE** 



BILL OF MATE	RIAL
PALLET, 35" X 45-1/2"	REQD

## GENERAL NOTES

- A. THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA1002. TO PRODUCE AN APPROVED UNIT LOAD, ALL PERTINENT PROCEDURES, SPECIFICATIONS AND CRITERIA SET FORTH WITHIN THE BASIC DRAWING WILL APPLY TO THE PROCEDURES DELINEATED IN THIS APPENDIX. ANY EXCEPTIONS TO THE BASIC PROCEDURES ARE SPECIFIED IN THIS APPENDIX.
- B. DIMENSIONS, CUBE AND WEIGHT OF A PALLET UNIT WILL VARY SLIGHTLY DEPENDING UPON THE ACTUAL DIMENSIONS OF THE BOXES AND THE WEIGHT OF THE SPECIFIC ITEM BEING UNITIZED.
- C. THE LOAD STRAPS MAY BE THREADED THROUGH THE STRAP SLOTS OF A PALLET OR PRE-POSITIONED ON THE PALLET DECK PRIOR TO PLACING BOXES ON THE PALLET. LOAD STRAPS MUST BE TENSIONED AND SEALED PRIOR TO APPLICATION OF TIEDOWN STRAPS.
- D. INSTALL EACH TIEDOWN STRAP TO PASS UNDER THE TOP DECK BOARDS OF THE PALLET AND TO BE LOCATED AS SHOWN. TIE-DOWN STRAPS WILL NOT BE APPLIED UNTIL THE LOAD STRAPS HAVE BEEN TENSIONED AND SEALED.
- E. THE FOLLOWING AMC (DARCOM) DRAWINGS ARE APPLICABLE FOR OUTLOADING AND STORAGE OF THE ITEMS COVERED BY THIS APPENDIX.

CARLOADING	DRAWING	19-48-4115-5PA 1002
TRUCKLOADING	DRAWING	19-48-4117-11PA 1003
STORAGE	DRAWING	19-48-4118-1-2-3-4-14-
	22PA 1002	

- F. FOR METHOD OF SECURING A STRAP CUTTER TO THE PALLET UNIT, SEE DARCOM DRAWING 19-48-4127-20P1000.
- G. IF LTEMS/COVERED HEREIN ARE UNITIZED PRIOR TO ISSUANCE OF THIS APPENDIX, THE BOXES NEED NOT BE REUNITIZED SOLELY TO CONFORM TO THIS APPENDIX.
- H. THE UNITIZATION PROCEDURES DEPICTED HEREIN MAY ALSO BE USED FOR UNITIZING HAND GRENADES WHEN IDENTIFIED BY DIFFERENT NATIONAL STOCK NUMBERS (NSN.) THAN WHAT IS SHOWN ON THE TITLE PAGE, PROVIDED THE BOX PACK DOES NOT VARY FROM WHAT IS DELINEATED HEREIN. THE EXPLOSIVE CLASSIFICATION OF OTHER ITEMS MAY BE DIFFERENT THAN WHAT IS SHOWN.
- J. THE STYLE 1A PALLET DELINEATED IN THE DETAIL AT LEFT NEED NOT HAVE CHAMFERS OR STRAP SLOTS AS SPECIFIED WITHIN MILITARY SPECIFICATION MIL-P-15011 WHEN USED FOR THE UNI-TIZATION OF THE ITEMS COVERED BY THIS APPENDIX.

