## APPENDIX 66D UNITIZATION PROCEDURES FOR BOXED AMMUNITION AND COMPONENTS ON 4-WAY ENTRY PALLETS


LAUNCHER, GRENADE, SMOKE, M243, PACKED ONE PER PLYWOOD BOX, UNITIZED I2 BOXES PER 40" X 48" PALLET; APPROX BOX SIZE 25"L X 20%" W X I4%" H

| PALLET UNIT DATA     |        |                       |             |             |               |        |  |  |
|----------------------|--------|-----------------------|-------------|-------------|---------------|--------|--|--|
| ITEMS IN             | CLUDED | HAZARD CLASSIFICATION |             |             |               | WEIGHT |  |  |
| NSN                  | DODIC  | DOT<br>CLASS          | CG<br>CLASS | QD<br>CLASS | COMP<br>GROUP | (LBS)  |  |  |
| 1055-<br>01-059-0560 |        | 1                     | INERT -     |             |               | 1,501  |  |  |

NOTICE: THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA1002.

| REVISIONS | DRAFTSMAN pt LAF WAX  |  |  |  |
|-----------|---|--|--|--|
|           | CHECKER LOG ENGAG OFFICE  WHI Ernst                                   |  |  |  |
|           | APPROVED US ARMY ARRAMENT, MUNITIONS AND CHEMICAL COMMAND  MORAL TOWN |  |  |  |
|           |   |  |  |  |
|           | APPROVED BY ORDER OF COMMANDING SENERAL, U.S. ARMY                    |  |  |  |
|           | U.S. ARMY DEFENSE AMMUNITION CENTER AND SCHOOL                        |  |  |  |
|           | U.S. ARMY AMC DRAWING   |  |  |  |
|           | SEPTEMBER 1987  |  |  |  |
|           | CLASS DIVISION DRAWING FILE   |  |  |  |
|           | 19 48 4116/ 20PA<br>66D 1002  |  |  |  |

DO NOT SCALE



## PALLET UNIT

SEE GENERAL NOTE "B" AT RIGHT,

| 12 BOXES OF GRENADE LAUNCHERS (1 PER BOX) @ 118 LBS | LBS (APPROX) |
|---|--------------|
|   | LBS          |
| TOTAL WEIGHT59.6                                    |              |


## **GENERAL NOTES**

- A. THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING
  19-48-4116-208A1002. TO PRODUCE AN APPROVED UNIT LOAD, ALL
  PERTINENT PROCEDURES, SPECIFICATIONS AND CRITERIA SET FORTH
  WITHIN THE BASIC DRAWING WILL APPLY TO THE BASIC PROCEDURES
  DELINEATED IN THIS APPENDIX. ANY EXCEPTIONS TO THE BASIC
  PROCEDURES ARE SPECIFIED IN THE APPENDIX.
- B. DIMENSIONS, CUBE AND WEIGHT OF A PALLET UNIT WILL VARY SLIGHTLY DEPENDING UPON THE ACTUAL DIMENSIONS OF THE BOXES AND THE WEIGHT OF THE SPECIFIC ITEM BEING UNITIZED,
- C. THE LOAD STRAPS WILL BE THREADED THROUGH THE STRAP SLOTS OF THE PALLET, LOAD STRAPS MUST BE TENSIONED AND SEALED PRIOR TO THE APPLICATION OF TIEDOWN STRAPS.
- D. INSTALL EACH TIEDOWN STRAP TO PASS UNDER THE TOP DECK BOARDS OF THE PALLET AND TO BE LOCATED AS SHOWN. TEDOWN STRAPS WILL NOT BE APPLIED UNTIL THE LOAD STRAPS HAVE BEEN TENSIONED AND SEALED.
- E, THE FOLLOWING AMC ( DARCOM ) DRAWINGS ARE APPLICABLE FOR OUTLOADING AND STORAGE OF ITEMS COVERED BY THIS APPENDIX.

CARLOADING ----- DRAWING 19-48-4115-5PA1002 TRUCKLOADING ---- DRAWING 19-48-4117-11PA1003 STORAGE ----- DRAWING 19-48-4118-1-2-3-4-14-22PA1002

- F. FOR METHOD OF SECURING A STRAP CUTTER TO THE PALLET UNIT, SEE DARCOM DRAWING 19-48-4127-20P1000.
- G. IF ITEMS COVERED HEREIN ARE UNITIZED PRIOR TO ISSUANCE OF THIS APPENDIX, THE BOXES NEED NOT BE REUNITIZED SOLELY TO CONFORM TO THIS APPENDIX.
- H. THE UNITIZATION PROCEDURES DEPICTED HEREIN MAY ALSO BE USED FOR UNITIZING GRENADE LAUNCHERS WHEN IDENTIFIED BY DIFFERENT NATIONAL STOCK NUMBERS (NSN) THAN WHAT IS SHOWN ON THE TITLE PAGE, PROVIDED THE BOX PACK DOES NOT VARY FROM WHAT IS DELINICATED HERBIN. THE EXPLOSIVE CLASSIFICATION OF OTHER ITEMS MAY BE DIFFERENT THAN WHAT IS SHOWN.
- J. WHEN THE UNIT LOAD DEPICTED AT LEFT IS TO BE USED FOR UNITIZING MARINE CORPS AMMUNITION, ONE LAYER OF BOXES MUST BE
  OMITTED, TEDOWN, STRAP LENGTHS MUST BE DECREASED TO 12'-11",
  AND LOAD STRAP LENGTHS MUST BE DECREASED TO 14'-4". THIS WILL
  RESULT IN AN OVERALL UNIT HEIGHT OF 34-3/4", A GROSS UNIT
  WEIGHT OF 1,028 POUNDS, AND A UNIT CUBE OF 42.0 CUBIC FEET,
  ADDITIONALLY, THE UNIT LOAD MAY BE MODIFIED AS DESCRIBED WHEN
  BEING SHIPPED BY MILVAN OR COMMERCIAL INTERMODAL FREIGHT
  CONTAINER, THE DETERMINATION TO REDUCE THE LOAD BY A LAYER
  FOR TRANSPORTATION WILL BE MADE BY THE RESPONSIBLE COMMAND
  AND WILL BE BASED UPON THE ECONOMICS OF TRANSPORTATION
  AND HANDLING,
- K. THE STYLE 1 PALLET DELINEATED IN THE DETAIL AT LEFT NEED NOT HAVE CHAMFERS OR STRAP SLOTS AS SPECIFIED WITHIN MILITARY SPECIFICATION MIL-P-15011 WHEN USED FOR THE UNITIZATION OF THE ITEMS COVERED BY THIS APPENDIX.

| BILL OF MATERIAL                  |          |
|-----------------------------------|----------|
| PALLET, 40" X 48"1 REQD           | 80 LBS   |
| STEEL STRAPPING, 3/4" 64.33' REQD | 4.60 LBS |
| SEAL FOR 3/4" STRAPPING 4 REQD    | NIL      |



PAGE 2