APPENDIX 80K

UNITIZATION PROCEDURES FOR BOXED AMMUNITION AND COMPONENTS ON 4-WAY ENTRY PALLETS


WARHEAD, 2.75 INCH ROCKET, PACKED 14 PER MK 12 MOD 0 METAL BOX, UNITIZED 20 BOXES PER 35" \times 45½" PALLET; APPROX BOX SIZE 18½" L X 9½" W X 12¾" H

PALLET UNIT DATA						
ITEMS INCLUDED		HAZARD CLASSIFICATION				WEIGHT
NSN	DODIC	DOT CLASS	CG CLASS	QD CLASS	COMP GROUP	(LBS)
1340- 00-038-8176	H837	Α	ΔΠ	1. 1	D	2, 271

NOTICE: THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA1002.

REVISION	-	Q WR	=/KBUU		
	CHECKER OH M APPROVED	W S ARMY ARMA	Sent	DINESS COMMAND	
	KO	APPROVED U S ARMY ARMAMENT MATERIEL READINESS HO DREAM OF THE DESCRIPTION OF THE DESCRIPT			
	DRSAR - CE	Y ORDER OF CO	DRSAN TMI	U S ARMY	
		APPROVED BY ORDER OF COMMANDING GENERAL U. S. ARBY MATERIED DEVLOPMENT AND READINESS COMMAND (DARCOM) U.S. ARBY DEFENSE AMMUNITION CENTER AND SCHOOL			
		U. S. ARMY DARCOM DRAWING			
	APRIL 19				
	CLASS	DIVISION	DRAWING	FILE	
	19	48	4116/ 80K	20PA 1002	

DO NOT SCALE




PALLET UNIT

SEE GENERAL NOTE "B" AT RIGHT.

20 BOXES OF WARHEADS (14 FER BOX) @ 110 LBS 2,200 DUNNAGE 6	
PALLET 65	1.3 S
TOTAL WEIGHT2,271	

BILL OF MATE	RIAL
PALLET, 35" X 45-1/2"	1 RE QD 65 LBS
STEEL STRAPPING, 3/4"	83.25' REQD 5.95 LBS
SEAL FOR 3/4" STRAPPING	7 REQD NIL



GENERAL NOTES

- A. THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION DRAWING 19-48-4116-20PA1002. TO PRODUCE AN APPROVED UNIT LOAD, ALL PERTINENT PROCEDURES, SPECIFICATIONS AND CRITERIA SET FORTH WITHIN THE BASIC DRAWING WILL APPLY TO THE PROCEDURES DELINEATED IN THIS APPENDIX. ANY EXCEPTIONS TO THE BASIC PROCEDURES ARE SPECIFIED IN THIS APPENDIX.
- B. DIMENSIONS, CUBE AND WEIGHT OF A PALLET UNIT WILL VARY SLIGHTLY DEPENDING UPON THE ACTUAL DIMENSIONS OF THE BOXES AND THE WEIGHT OF THE SPECIFIC ITEM BEING UNITIZED.
- C. THE LOAD STRAPS WILL BE THREADED THROUGH THE STRAP SLOTS OF A PALLET OR PRE-POSITIONED ON THE PALLET DECK PRIOR TO PLACING BOXES ON THE PALLET.
- D. INSTALL EACH TIEDOWN STRAP TO PASS UNDER THE DECK/STRINGER BOARDS OF THE PALLET AND TO BE LOCATED AS SHOWN. TEDOWN STRAPS WILL NOT BE APPLIED UNTIL THE LOAD STRAPS HAVE BEEN TEN-SIONED AND SPALED.
- E. THE FOLLOWING DARCOM DRAWINGS ARE APPLICABLE FOR OUTLOADING AND STORAGE OF THE ITEMS COVERED BY THIS APPENDIX.

CARLOADINGDRAWING	19-48-4115-5PA1002
TRUC KLOADING DRAWING	19-48-4117-11PA 1003
STORAGEDRAWING	19-48-4118-1-2-3-4-14-
	22PA 1002

- F. FOR METHOD OF SECURING A STRAP CUTTER TO THE PALLET UNIT, SEE DARCOM DRAWING 19-48-4127-20P1000.
- G. IF ITEMS COVERED HEREIN ARE UNITIZED PRIOR TO ISSUANCE OF THIS APPENDIX, THE BOXES NEED NOT BE REUNITIZED SOLELY TO CONFORM TO THIS APPENDIX.
- H. THE UNITIZATION PROCEDURES DEPICTED HEREIN MAY ALSO BE USED FOR UNITIZING WARHEADS WHEN IDENTIFIED BY DIFFERENT NATIONAL STOCK NUMBERS (NSW) THAN WHAT IS SHOWN ON THE TITLE PAGE, PROVIDED THE BOX PACK DOES NOT VARY FROM WHAT IS DELINEATED HEREIN. THE EXPLOSIVE CLASSFICATION OF OTHER ITEMS MAY BE DIFFERENT THAN WHAT IS SHOWN.