APPENDIX 95S

UNITIZATION PROCEDURES FOR BOXED AMMUNITION AND COMPONENTS ON 4-WAY ENTRY PALLETS

MINE, ANTI-PERSONNEL, M14, 90 PER BOX, UNITIZED 30 BOXES PER 40" X 48" PALLET; APPROX BOX SIZE 20" L X 17-9/16" W X 8-15/16" H

NOTICE: THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA1002.

DISTRIBUTION STATEMENT A.


APPROVED FOR PUBLIC RELEASE:
DISTRIBUTION IS UNLIMITED.

U.S. ARMY MATERIEL COMMAND DRAWING DRAFTSMAN BETTY J. KUNDERT APPROVED, U.S. ARMY INDUSTRIAL OPERATIONS COMMAND SANDRA M. ENGINEER SCHULTZ SUPPLY ENGINEERING TRANSPORTATION VALIDATION NOIZIVID ENGINEERING ENGINEERING NOIZIVID DIVIZION LMT-012MA AMSTA-AR-ESK APPROVED BY ORDER OF COMMANDING GENERAL, U.S. ARMY MATERIEL COMMAND Main J Ernst JANUARY 1997 U.S. ARH DEFENSE AMMUNITION CEN CLASS NOIZIVIO DRAWING FILE 4116/ 20PA 48 19 952 1002

DO NOT SCALE

PALLET UNIT DATA					
ITEMS INCLUDED		HAZARD CLASS AND DIVISION •		APPROX	
NZN	DODIC	OD CLASS	COMP GROUP	WEIGHT LBS	
1345- 00-028-5108 00-096-3093	K121 K121	1 . 1 1 . 1		1,588 1,588	

HAZARD CLASSIFICATION DATA CONTAINED IN THE ABOVE CHART IS FOR GUIDANCE AND INFORMATIONAL PURPOSES ONLY. VERIFICATION OF THE SPECIFIED DATA SHOULD BE MADE BY CONSULTING THE MOST RECENT JOINT HAZARD CLASSIFICATION SYSTEM LISTING OR OTHER APPROVED LISTING(S).



PALLET UNIT

SEE GENERAL NOTE "B" AT RIGHT.

30 BOXES OF M14 MINES (90 PER BOX) AT 50 LBS - - - - - 1,500 LBS (APPROX) DUNNAGE - - - - - - - - - 8 LBS PALLET - - - - - - - - - - - - - - - - 80 LBS

TOTAL WEIGHT - - - - - - - - - - 1,588 LBS (APPROX) CUBE - - - - - - - - 61.2 CU FT (APPROX)

GENERAL NOTES


- A. THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA1002. TO PRODUCE AN APPROVED UNIT LOAD, ALL PERTINENT PROCEDURES, SPECIFICATIONS AND CRITERIA SET FORTH WITHIN THE BASIC DRAWING WILL APPLY TO THE PROCEDURES DELINEATED IN THIS APPENDIX. ANY EXCEPTIONS TO THE BASIC PROCEDURES ARE SPECIFIED IN THIS APPENDIX.
- B. DIMENSIONS, CUBE AND WEIGHT OF A PALLET UNIT WILL VARY SLIGHTLY DEPENDING UPON THE ACTUAL DIMENSIONS OF THE BOXES AND THE WEIGHT OF THE SPECIFIC ITEM REING UNITIZED.
- C. THE LOAD STRAPS MAY BE THREADED THROUGH THE STRAP SLOTS OF A PALLET OR PRE-POSITIONED ON THE PALLET DECK PRIOR TO PLACING BOXES ON THE PALLET. LOAD STRAPS MUST BE TENSIONED AND SEALED PRIOR TO APPLICATION OF TIEDOWN STRAPS.
- . INSTALL EACH TIEDOWN STRAP TO PASS UNDER THE DECK BOARDS OF THE PALLET AND TO BE LOCATED AS SHOWN. TIEDOWN STRAPS WILL NOT BE APPLIED UNTIL THE LOAD STRAPS HAVE BEEN TENSIONED AND SEALED.
- E. THE FOLLOWING AMC DRAWINGS ARE APPLICABLE FOR OUTLOADING AND STORAGE OF THE ITEMS COVERED BY THIS APPENDIX.

CARLOADING - - - 19-48-4115-5PA1002
TRUCKLOADING - - 19-48-4117-11PA1003
STORAGE - - - 19-48-4118-1-2-3-4-14-22PA1002
END OPENING ISO
CONTAINER - - 19-48-4153-15PA1002
MILVAN - - - 19-48-4166-15PA1003

SIDE OPENING ISO CONTAINER - - - 19-48-4267-15PA1009

- F. IF ITEMS COVERED HEREIN ARE UNITIZED PRIOR TO ISSUANCE OF THIS APPENDIX, THE BOXES NEED NOT BE REUNITIZED SOLELY TO CONFORM TO THIS APPENDIX
- G. THE UNITIZATION PROCEDURES DEPICTED HEREIN MAY ALSO BE USED FOR UNITIZING M14 MINES WHEN IDENTIFIED BY DIFFERENT NATIONAL STOCK NUMBERS (NSN) THAN WHAT IS SHOWN ON PAGE 2, PROVIDED THE BOX PACK DOES NOT VARY FROM WHAT IS DELINEATED HEREIN. THE EXPLOSIVE CLASSIFICATION OF OTHER ITEMS MAY BE DIFFERENT THAN WHAT IS SHOWN.
- H. THE STYLE ! PALLET DELINEATED IN THE DETAIL AT LEFT NEED NOT HAVE CHAMFERS OR STRAP SLOTS AS SPECIFIED WITHIN MILITARY SPECIFICATION MIL-P-15011 WHEN USED FOR THE UNITIZATION OF ITEMS COVERED BY THIS APPENDIX.
- J. FOR DETAILS OF THE MIL-B-2427 WOODEN BOX SEE DRAWING 8861849.

BILL OF MATERIAL					
PALLET, 40" X 48" 1 R STEEL STRAPPING, 3/4" 80.42' R					
SEAL FOR 3/4" STRAPPING 5 R	EQD NIL				



FILLER ASSEMBLY

(FOR MINUS ONE BOX)