APPENDIX 96E

UNITIZATION PROCEDURES FOR BOXED AMMUNITION AND COMPONENTS ON 4-WAY ENTRY PALLETS

FUZE, MINE, AT, M607 PACKED IOO PER WOODEN BOX, UNITIZED I2 BOXES PER 35" X $45\frac{1}{2}$ " PALLET; APPROX BOX SIZE $19\frac{1}{8}$ "L X $16\frac{13}{16}$ "W X $17\frac{19}{32}$ "H


PALLET UNIT DATA							
ITEMS INCLUDED		НА	WEIGHT				
NSN	DODIC	DOT CLASS	CG CLASS	QD CLASS	COMP GROUP	(LBS)	
1345- 00-828-7458		С	ш	1.4	D	1,055	

NOTICE: THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4116-20PA1002.

● HAZARD CLASSIFICATION DATA CONTAINED IN THE ABOVE CHART IS FOR GUIDANCE AND INFORMATIONAL PURPOSES ONLY. VERIFICATION OF THE SPECIFIED DATA SHOULD BE MADE BY CONSULTING THE MOST RECENT JOINT HAZARD CLASSIFICATION SYSTEM LISTING OR OTHER APPROVED LISTING (S).

REVIS	DOAFTSMAN	dh LAI	WRF			
		2524	lwa	Hang office		
		DWartin 15.9 St. anon				
		Martin S. J. S. adam				
		CONTRACTOR OF CO				
		U.S. ARMY AMC DRAWING				
$ \cdot \cdot \wedge $		JUNE 1986				
		CLASS	DIVISION	DRAWING	FILE	
		19	48	4116/	20PA	
				96E	1002	

DO NOT SCALE



TOTAL WEIGHT-

----- 65 LBS --- 1,055 LBS (APPROX)

--- 45.6 CU FT (APPROX)

GENERAL NOTES

- A. THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING
 19-48-4116-20PA1002. TO PRODUCE AN APPROVED UNIT LOAD, ALL
 PERTINENT PROCEDURES, SPECIFICATIONS AND CRITERIA SET FORTH
 WITHIN THE BASIC DRAWING WILL APPLY TO THE PROCEDURES
 DELINEATED IN THIS APPENDIX. ANY EXCEPTIONS TO THE BASIC
 PROCEDURES ARE SPECIFIED IN THIS APPENDIX.
- B. DIMENSIONS, CUBE AND WEIGHT OF A PALLET UNIT WILL VARY SLIGHTLY DEPENDING UPON THE ACTUAL DIMENSIONS OF THE BOXES AND THE WEIGHT OF THE SPECIFIC ITEM BEING UNITIZED.
- C. THE LOAD STRAPS MAY BE THREADED THROUGH THE STRAP SLOTS OF A PALLET OR PRE-POSITIONED ON THE PALLET DECK PRIOR TO PLACING BOXES ON THE PALLET. LOAD STRAPS MUST BE TEN-SIONED AND SEALED PRIOR TO APPLICATION OF TIEDOWN STRAPS.
- D. INSTALL EACH TIEDOWN STRAP TO PASS UNDER THE TOP DECK/ STRINGER BOARDS OF THE PALLET AND TO BE LOCATED AS SHOWN. TEDOWN STRAPS WILL NOT BE APPLIED UNTIL THE LOAD STRAPS HAVE BEEN TENSIONED AND SEALED.
- E. THE FOLLOWING AMC (DARCOM) DRAWINGS ARE APPLICABLE FOR OUTLOADING AND STORAGE OF THE ITEMS COVERED BY THIS APPENDIX.

CARLOADING----- DRAWING 19-48-4115-5PA1002 TRUCKLOADING -- DRAWING 19-48-4117-11PA1003 STORAGE------ DRAWING 19-48-4118-1-2-3-4-14-22PA1002

- F. FOR METHOD OF SECURING A STRAP CUTTER TO THE PALLET UNIT, SEE DARCOM DRAWING 19-48-4127-20P1000.
- G. IF ITEMS COVERED HEREIN ARE UNITIZED PRIOR TO ISSUANCE OF THIS APPENDIX, THE BOXES NEED NOT BE REUNITIZED SOLELY TO CONFORM TO THIS APPENDIX.
- H. THE UNITIZATION PROCEDURES DEPICTED HEREIN MAY ALSO BE USED FOR UNITIZING MINE FUZES WHEN IDENTIFIED BY DIFFERENT NATIONAL STOCK NUMBERS (NSN.) THAN WHAT IS SHOWN ON THE TITLE PAGE, PROVIDED THE BOX PACK DOES NOT VARY FROM WHAT IS DELINEATED HEREIN. THE EXPLOSIVE CLASSIFICATION OF OTHER ITEMS MAY BE DIFFERENT THAN WHAT IS SHOWN.

BILL OF MATERIAL							
PALLET, 35" X 45-1/2"1	REQD 65 LBS						
STEEL STRAPPING, 3/4" 70.83' SEAL FOR 3/4" STRAPPING 5							

PALLET .

