APPENDIX 2A

UNITIZATION PROCEDURES FOR BOXED WHITE PHOSPHORUS (WP) AND PLASTICIZED WHITE PHOSPHORUS (PWP) LOADED AMMUNITION ON 4-WAY ENTRY PALLETS


CARTRIDGE, 60MM, PACKED 8 PER WOODEN BOX, UNITIZED 60 BOXES PER 40" X 48" PALLET; APPROX BOX SIZE $14\frac{5}{8}$ " L X $10\frac{1}{8}$ " W X $6\frac{7}{8}$ " H

PALLET UNIT DATA									
ITEMS INCLUDED HAZARD CLASSIFICATION					TION	WEIGHT			
NSN	DODIC	DOT CLASS	CG CLASS	QD CLASS	COMP GROUP	(LBS)			
1310- 00-782 - 5517	B630	A	П-D	(12) 1. 2	Н	3, 027			

NOTICE: THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4015-20PA1004.

REVISIONS		DRAFTSMAN LN	pt _{WR}	=/ww	
		1	J. S. ARMY ARMA	MENT MATERIEL REAL	
		APPROVED E MATERIEL DI	Y ORDER OF COM	MANDING GENERAL O READINESS COMMA	U.S. ARMY
				ARCOM D	
		FEBRUARY 1983			
		CLASS	DIVISION	DRAWING	FILE
		19	48	4015/2A	20PA 1004

DO NOT SCALE



PALLET UNIT

SEE GENERAL NOTE "B" AT RIGHT.

60 BOXES OF 60MM CARTRIDGES (8 PER BOX) @ 49 LBS2,940 DUNNAGE7 PALL'ET80	LBS
TOTAL WEIGHT3,027 CUBE42.0 C	

BILL OF MATERIAL					
PALLET, 40" X 48"	LBS				

GENERAL NOTES

- A. THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTIONWITH THE BASIC UNITIZATION PROCEDURES DRAW-ING 19-48-4015-20PA1004. TO PRODUCE AN APPROVED UNIT LOAD, ALL PERTINENT PROCEDURES, SPECIFICATIONS AND CRITERIA SET FORTH WITHIN THE BASIC DRAWING WILL APPLY TO THE PRO-CEDURES DELINEATED IN THIS APPENDIX. ANY EXCEPTIONS TO THE BASIC PROCEDURES ARE SPECIFIED IN THIS APPENDIX.
- B. DIMENSIONS, CUBE AND WEIGHT OF A PALLET UNIT WILL VARY SLIGHTLY DEPENDING UPON THE ACTUAL DIMENSIONS OF THE BOXES AND THE WEIGHT OF THE SPECIFIC ITEM BEING UNITIZED.
- C. INSTALL EACH HORIZONTAL STRAP TO TO ENCIRCLE A LAYER OF BOXES ON THE PALLET, HORIZONTAL STRAPS MUST BE TENSION-ED AND SEALED PRIOR TO APPLICATION OF TIEDOWN STRAPS.
- D. INSTALL EACH TIEDOWN STRAP TO PASS UNDER THE DECK/STRING-ER BOARDS OF THE PALLET AND TO BE LOCATED AS SHOWN. TIE-DOWN STRAPS WILL NOT BE APPLIED UNTIL THE HORIZONTAL STRAPS HAVE BEEN TENSIONED AND SEALED,
- E. THE FOLLOWING DARCOM DRAWINGS ARE APPLICABLE FOR OUT-LOADING AND STORAGE OF THE ITEMS COVERED BY THIS APPENDIX.

CARLCADING------DRAWING 19-48-4115-5PA1002 TRUCKLOADING -----DRAWING 19-48-4117-11PA1003 STORAGE ----- DRAWING 19-48-4118-1-2-3-4-14-22PA1002

- F. FOR METHOD OF SECURING A STRAP CUTTER TO THE PALLET UNIT, SEE DARCOM DRAWING 19-48-4127-20P1000.
- G. IF ITEMS COVERED HEREIN ARE UNITIZED PRIOR TO ISSUANCE OF THIS APPENDIX, THE BOXES NEED NOT BE REUNITIZED SOLELY TO CONFORM TO THIS APPENDIX.
- H. THE UNITIZATION PROCEDURES DEPICTED HEREIN MAY ALSO BE USED FOR UNITIZING 60MM CARTRIDGES, WHEN IDENTIFIED BY DIFFERENT NATIONAL STOCK NUMBERS (NSN.) THAN WHAT IS SHOWN ON THE TITLE PAGE, ROVIDED THE BOX PACK DOES NOT VARY FROM WHAT IS DELINEATED HEREIN. THE EXPLOSIVE CLASSIFICATION OF OTHER ITEMS MAY BE DIFFERENT THAN WHAT IS SHOWN.

