APPENDIX 3B

UNITIZATION PROCEDURES FOR BOXED WHITE PHOSPHORUS (WP) AND PLASTICIZED WHITE PHOSPHORUS (PWP) LOADED AMMUNITION ON 4-WAY ENTRY PALLETS


CARTRIDGE, 75MM, PACKED 2 PER WOODEN BOX, UNITIZED 20 BOXES PER 35" X $45\frac{1}{2}$ " PALLET; APPROX BOX SIZE $34\frac{1}{8}$ " L X $11\frac{1}{2}$ " W X $7\frac{1}{4}$ " H

PALLET UNIT DATA									
ITEMS INCLUDED			WELOUT						
NSN	DODIC	DOT CLASS	CG CLASS	QD CLASS	COMP GROUP	(LBS)			
1315- 00-028-4649 00-028-4650	C056 C056	A A	П-D П-D	(12) 1. 2 (12) 1. 2	H H	1, 690 1, 550			

NOTICE: THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4015-20PA1004.

REVISIONS	Draftsman Diw CHECKER	pt _{WR}	NG (W)		
	GRG/	J S. ARMY ARMAI	MENT MATERIEL REAL	DINESS COMMAND	
	DREAR-LEP DREAR-				
	U. S. ARMY DARCOM DRAWING				
	FEBRUARY 1983				
	CLASS	DIVISION	DRAWING	FILE	
	19	48	4015/ 3B	20 PA 1004	

DO NOT SCALE



GENERAL NOTES

- A. THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CON-JUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4015-20PA1004. TO PRODUCE AN APPROVED UNIT LOAD, ALL PRITINENT PROCEDURES, SPECIFICATIONS AND CRITERIA SET FORTH WITHIN THE BASIC DRAWING WILL APPLY TO THE PROCEDURES DELINEATED IN THIS APPENDIX. ANY EXCEPTIONS TO THE BASIC PROCEDURES ARE SPECIFIED IN THIS APPENDIX.
- B. DIMENSIONS, CUBE AND WEIGHT OF A PALLET UNIT WILL VARY SLIGHTLY DEPENDING UPON THE ACTUAL DIMENSIONS OF THE BOXES AND THE WEIGHT OF THE SPECIFIC ITEM BEING UNITIZED.
- C. INSTALL THE HORIZONTAL STRAP TO ENCIRCLE THE LAYER OF BOXES ON THE PALLET. HORIZONTAL STRAP MUST BE TENSIONED AND SEALED PRIOR TO APPLICATION OF TIEDOWN STRAPS.
- D. INSTALL EACH TIEDOWN STRAP TO PASS UNDER THE DECK/STRINGER BOARDS OF THE PALLET AND TO BE LOCATED AS SHOWN. TIEDOWN STRAPS WILL NOT BE APPLIED UNTIL THE HORIZONTAL STRAP HAS BEFN TENSIONED AND SEALED.
- E. THE FOLLOWING DARCOM DRAWINGS ARE APPLICABLE FOR OUT-LOADING AND STORAGE OF THE ITEMS COVERED BY THIS APPENDIX.

CARLOADING------ DRAWING 19-48-4115-5PA 1002 TRUCKLOADING------ DRAWING 19-48-4117-11PA 1003 STORAGE------DRAWING 19-48-4118-1-2-3-4-14-22PA 1002

- F. FOR METHOD OF SECURING A STRAP CUTTER TO THE PALLET UNIT, SEE DARCOM DRAWING 19-48-4127-20P1000.
- G. IF ITEMS COVERED HEREIN ARE UNITIZED PRIOR TO ISSUANCE OF THIS APPENDIX, THE BOXES NEED NOT BE REUNITIZED SOLELY TO CONFORM TO THIS APPENDIX.
- H. THE UNITIZATION PROCEDURES DEPICTED HEREIN MAY ALSO BE USED FOR UNITIZING 75MM CARTRIDGES WHEN IDENTIFIED BY DIFFERENT NATIONAL STOCK NUMBERS (NSN) THAN WHAT IS SHOWN ON THE TITLE PAGE, PROVIDED THE BOX PACK DOES NOT VARY FROM WHAT IS DELINFATED HEREIN. THE EXPLOSIVE CLASSIFICATION OF OTHER ITEMS MAY BE DIFFERENT THAN WHAT IS SHOWN.
- J. IF THERE IS A NEED TO USE FILLER ASSEMBLIES AND AT LEAST TWO PALLET UNITS ARE BEING CONSTRUCTED, NOT MORE THAN 16 FILLERS WILL BE INSTALLED IN ANY ONE PALLET UNIT, ADDITIONAL FILLERS CAN BE PUT IN A SECOND PALLET UNIT AS REQUIRED WHEN THE QUANTITY OF 16 FILLERS IN THE FIRST REDUCED PALLET UNIT IS INSUFFICIENT TO SATISFY THE TOTAL REDUCTION NEEDED. USING TWO PALLET UNITS TO SATISFY THE PALLETIZATION CRITERIA APPLICABLE TO LESS-THAN-FULL PALLET UNITS IS AN EXCEPTION TO THE BASIC PROCEDURES. HOWEVER, THE EXCEPTION IS NECESSARY FOR THE AMMUNITION PACK COVERED BY THIS APPENDIX, TO MOST EFFECTIVELY GET AN ACCEPTABLE, COMPACT AND SOUND PALLET UNITS.

TIE PIECE, 1" X 4" X BOX HEIGHT (2 REQD). NAIL TO LONGITUDINAL PIECES W/2-6d NAILS


SEE GENERAL NOTE "B" AT RIGHT.

DUNNAGE ----

20 BOXES OF 75MM CARTRIDGES (2 PER BOX) @ 81 LBS -----1,620 LBS (APPROX)

_____ 65 LBS

TOTAL WEIGHT-----1,690 LBS (APPROX)
CUBE -----38.2 CU FT (APPROX)



-STRAP BEARING PIECE, 2" X 4" BY BOX HEIGHT MINUS 3" (AS REQD).
NAIL TO VERTICAL PIECES W/2-10d NAILS AT EACH END. NOTE: WHEN A
UNIT HAS MORE THAN SIX BOXES OMITTED, THE FILLER ASSEMBLY OR
ASSEMBLIES LOCATED IN AN OUTER STACK ON THE 35" SIDE OR SIDES OF
THE PALLET WILL REQUIRE A "STRAP BEARING PIECE" UNDER THE HORIZONTAL
STRAP. STAPLE STRAP TO STRAP BEARING PIECE.

FILL PIECE, 2" X 4" X CUT-TO-FIT (AS REQD). NAIL TO THE VERTICAL PIECE W/3-10d NAILS. NOTE: WHEN A UNIT HAS MORE THAN 12 BOXES OMITTED, THE FILLER ASSEMBLY OR ASSEMBLIES LOCATED IN A OUTER STACK ON THE 45-1/2" SIDE OR SIDES OF THE PALLET UNIT WILL REQUIRE FILL PIECES. STAPLE STRAP TO THE "FILL PIECES."

LATERAL PIECE, 2" X 4" X BOX HEIGHT MINUS 3" (4 REQD). NAIL TO THE VERTICAL PIECES W/2-10d NAILS AT EACH END.

FILLER ASSEMBLY

(FOR MINUS ONE BOX)

PAGE 2