APPENDIX IOI

UNITIZATION PROCEDURES FOR BOXED AMMUNITION AND COMPONENTS ON SKIDDED BASES


FLARE, AIRCRAFT, PACKED 2 PER WOODEN BOX, UNITIZED 16 BOXES PER TYPE I SKID BASE; APPROX BOX SIZE $28\frac{5}{8}$ " L X $11\frac{7}{16}$ " W X $6\frac{29}{32}$ " H

SKIDDED UNIT DATA									
ITEMS INCLUDED		н	WEIGHT						
NSN	DODIC	DOT CLASS	CG CLASS	QD CLASS	COMP GROUP	(LBS)			
1370-00 028-5931	L388	В	II-C	1.3	G	1,002			

NOTICE: THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4138-20PA1000.

REVISIONS			CHECKER	RMNZ	7.		
			RSH-C	SRG JUL	AMENT MATERIEL	READINESS COMMAND	
	-V	· · · · · · · · · · · · · · · · · · ·	BARBenton Davide Fatty				
			APPROVED &	Y ORDER OF COM	MANONS GENERAL, D READWESS COMM	U. S. ARMY AND (DARCOM)	
			U.S. ARMY DEFENDE AMMANTION CENTER AND SCHOOL				
			U. S. ARMY DARCOM DRAWING				
			FEBRUARY 1981				
			CLASS	DIVISION	DRAWING	FILE	
			19	48	4138/101	20PA	
						1000	

DO NOT SCALE



TOTAL WEIGHT ------1,002 LBS (APPROX)

16 BOXES (FLARE, AIRCRAFT; 2 PER BOX) @ 60 LBS ----- 960 LBS (APPROX)

SEE GENERAL NOTE "B" AT RIGHT.

CUBE -----25.3 CU FT (APPROX)

----- 4 LBS (APPROX)

BILL OF MATERIAL

DUNNAGE ---


TYPE I SKID BASE, 19-1/8" W X 44-3/4" L -- 1 REQD -- 38 LBS STEEL STRAPPING, 3/4" ------ 55.33' REQD -- 3.95 LBS SEAL FOR 3/4" STRAPPING ------ 4 REQD -- NIL


GENERAL NOTES

- A. THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4138-20PA1000. TO PRODUCE AN APPROVED UNIT LOAD, ALL PERTINENT PROCEDURES, SPECIFICATIONS AND CRITERIA SET FORTH WITHIN THE BASIC DRAWING WILL APPLY TO THE PROCEDURES DELINEATED IN THIS APPENDIX. ANY EXCEPTIONS TO THE BASIC PROCEDURES ARE SPECIFIED IN THIS APPENDIX.
- B. DIMENSIONS, CUBE AND WEIGHT OF A SKIDDED UNIT WILL VARY SLIGHTLY DEPENDING UPON THE ACTUAL DIMENSIONS OF THE BOXES AND THE WEIGHT OF THE SPECIFIC ITEM BEING UNITIZED.
- C. THE FOLLOWING DARCOM DRAWINGS ARE APPLICABLE FOR OUTLOADING AND STORAGE OF THE !TEMS COVERED BY THIS APPENDIX.

CARLOADING ------ DRAWING 19-48-4123-5PA1003
TRUCKLOADING ------ DRAWING 19-48-4124-11PA1004
STORAGE ----- DRAWING 19-48-4125-1-2-14PA1003

- D. FOR METHOD OF SECURING A STRAP CUTTER TO THE SKIDDED UNIT, SEE DARCOM DRAWING 19-48-4127-20P1000.
- E. IF ITEMS COVERED HEREIN ARE UNITIZED PRIOR TO ISSUANCE OF THIS APPENDIX, THE BOXES NEED NOT BE REUNITIZED SOLELY TO CONFORM TO THIS APPENDIX.
- THE UNITIZATION PROCEDURES DEPICTED HEREIN MAY ALSO BE USED FOR UNITIZING AIRCRAFT FLARES WHEN IDENTIFIED BY DIFFERENT NATIONAL STOCK NUMBERS (NSN) THAN WHAT IS SHOWN ON THE TITLE PAGE, PROVIDED THE BOX PACK DOES NOT VARY FROM WHAT IS DELINEATED HEREIN. THE EXPLOSIVE CLASSIFICATION OF OTHER ITEMS MAY BE DIFFERENT THAN WHAT IS SELOWN.
- G. NOTE: A TYPE II SKID BASE IS NOT APPROVED FOR USE IN UNITIZING THESE ITEMS. SEE GENERAL NOTE "B" ON PAGE 2 OF THE BASIC PROCEDURES DRAWING 19-48-4138-20PA1000.





PAGE 2