APPENDIX 108

UNITIZATION PROCEDURES FOR BOXED AMMUNITION AND COMPONENTS ON SKIDDED BASES


LAUNCHER, GRENADE, SMOKE, PACKED ONE PER PLYWOOD BOX, UNITIZED 4 BOXES PER TYPE II SKID BASE; APPROX BOX SIZE 28" L X 28" W X 18" H

SKIDDED UNIT DATA							
ITEMS INCLUDED		HAZARD CLASSIFICATION				WE IGHT	
NSN	DOD IC	DOT CLASS	CG CLASS	QD CLASS	COMP GROUP	(LBS)	
1040- 01-015-0874			INERT -			991	

NOTICE: THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4138-20PA1000.

REVISIONS	BLZ do RAR WRF			
	CHECKER LOGEMOND OFFICE GREG LUCKY			
	APPROVED US AND VARIABLEST, EMPIRITIONS AND CHESICAL CONTROL OF THE PROPERTY O			
	APPROVED BY COMER OF COMMANGING SEMERAL, U.S. ARMY			
	US ARMY DEFENSE AMMUNITION CENTER AND SCHOOL			
	U.S. ARMY AMC DRAWING			
	JANUARY 1985			
	CLASS DIVISION DRAWING FILE			
	19 48 4138/ 20PA 108 1000			

DO NOT SCALE



TOTAL WEIGHT --- 991 LBS (APPROX)
CUBE ----- 37.2 CU FT (APPROX)

BILL OF MATERIAL TYPE II SKID BASE, 24" W X 56" L --- 1 REQD ------ 26 LBS STEEL STRAPPING, 3/4" ------- 65.33' REQD ------ 4.67 LBS SEAL FOR 3/4" STRAPPING ------ 4 REQD ------ NIL

GENERAL NOTES

- A. THIS APPENDIX CANNOT STAND ALONE BUT MUST BE USED IN CONJUNCTION WITH THE BASIC UNITIZATION PROCEDURES DRAWING 19-48-4138-20PA1000. TO PRODUCE AN APPROVED UNIT LOAD, ALL PERTINENT PROCEDURES, SPECIFICATIONS AND CRITERIA SET FORTH WITHIN THE BASIC DRAWING WILL APPLY TO THE PROCEDURES DELINEATED IN THIS APPENDIX. ANY EXCEPTIONS TO THE BASIC PROCEDURES ARE SPECIFIED IN THIS APPENDIX.
- B. DIMENSIONS, CUBE AND WEIGHT OF A SKIDDED UNIT WILL VARY SLIGHTLY DEPENDING UPON THE ACTUAL DIMENSIONS OF THE BOXES AND THE WEIGHT OF THE SPECIFIC ITEM BEING UNITIZED.
- C. ONLY A TYPE II SKID BASE WILL BE USED TO ASSEMBLE THIS UNIT. THE
 "W" DIMERSION OF THE SKID BASE WILL BE 24" AND THE "L" DIMENSION
 WILL BE 56". NOTE: A TYPE I SKID BASE IS NOT APPROVED FOR USE IN
 UNITIZING THIS ITEM.
- D. WHEN A FILLER ASSEMBLY IS USED IN A UNIT LOAD, THE TIEDOWN STRAPS WILL BE STAPLED TO THE TOP LONGITUDINAL PIECES OF THE ASSEMBLY.
- E. THE FOLLOWING AMC (DARCOM) DRAWINGS ARE APPLICABLE FOR OUT-LOADING AND STORAGE OF THE ITEMS COVERED BY THIS APPENDIX.

CARLOADING ------ DRAWING 19-48-4123-5PA1003
TRUCKLOADING ------ DRAWING 19-48-4124-11PA1004
STORAGE ----- DRAWING 19-48-4125-1-2-3-4-14-22PA1003

- F. FOR METHOD OF SECURING A STRAP CUTTER TO THE PALLET UNIT, SEE DARCOM DRAWING 19-48-4127-20P1000.
- G. IF ITEMS COVERED HEREIN ARE UNITIZED PRIOR TO ISSUANCE OF THIS APPENDIX, THE BOXES NEED NOT BE REUNITIZED SOLELY TO CONFORM TO THIS APPENDIX.
- H. THE UNITIZATION PROCEDURES DEPICTED HEREIN MAY ALSO BE USED FOR UNITIZING GRENADE LAUNCHERS, WHEN IDENTIFIED BY DIFFERENT NATIONAL STOCK NUMBERS (NSN) THAN WHAT IS SHOWN ON THE TITLE PAGE, PROVIDED THE BOX PACK DOES NOT VARY FROM WHAT IS DELINEATED HEREIN. THE EXPLOSIVE CLASSIFICATION OF OTHER ITEMS MAY BE DIFFERENT THAN WHAT IS SHOWN.

