

STORAGE IN APPROVED MAGAZINES OF COMPLETE ROUNDS* PACKED IN CYLINDRICAL METAL CONTAINERS ON 4-WAY ENTRY PALLETS

M18 SERIES CONTAINER (WITH PROTECTIVE COVER)

INDEX

ITEM	PAGE(S)
GENERAL NOTES AND MATERIAL SPECIFICATIONS - - - - -	2
PALLET UNIT DETAILS - - - - -	3
STORAGE PROCEDURES (EARTH COVERED MAGAZINES):	
81'-0", 60'-8" AND 40'-4" L X 26'-6" W X 12'-9" H IGLOO MAGAZINES - -	4,5
81'-2" L X 26'-6" W X 12'-1-3/4" H ARCH TYPE MAGAZINE - - - - -	6,7
80'-0" AND 40'-0" L X 25'-0" W X 12'-1-3/4" H ARCH TYPE MAGAZINES - -	8,9
80'-0" AND 40'-0" L X 25'-0" W X 11'-0" H ARCH TYPE MAGAZINES - - -	10,11
80'-0" AND 40'-0" L X 25'-0" W X 10'-0" H ARCH TYPE MAGAZINES - - -	12,13
80'-0" L X 25'-0" W X 14'-0" H STRADLEY AND	
89'-0" L X 24'-10" W X 14'-4" H OVAL ARCH MAGAZINES - - - - -	14,15
89'-0" L X 24'-11" W X 13'-6" H STEEL ARCH MAGAZINE - - - - -	16,17
52'-0" AND 44'-7" DIA CORBETTA MAGAZINES - - - - -	18,19
100'-8" L X 50'-0" W RECTANGULAR MAGAZINE - - - - -	20,21
60'-0" L X 40'-0" W X 15'-0" H TYPE II BUNKER - - - - -	22,23
60'-0" L X 40'-0" W X 11'-0" TYPE III BUNKER - - - - -	24,25
40'-0" L X 20'-0" W X 11'-0" H TYPE IV BUNKER - - - - -	26,27
TYPICAL MULTIPLE-LOT STORAGE PROCEDURES:	
IGLOO AND ARCH TYPE MAGAZINES - - - - -	28,29
STRADLEY AND OVAL ARCH TYPE MAGAZINES - - - - -	30,31
CORBETTA MAGAZINE - - - - -	32,33
RECTANGULAR MAGAZINE - - - - -	34
BUNKERS - - - - -	35,36

* PROCEDURES WITHIN THIS DRAWING APPLY TO DEMOLITION CRATERING CHARGES.

U. S. ARMY MATERIEL COMMAND DRAWING			
APPROVED, U. S. ARMY INDUSTRIAL OPERATIONS COMMAND <i>DLH</i> <i>David A. Pistoich</i> AMSTA-AR-ESK	DRAFTSMAN	D. WHITMORE	
	ENGINEER	M. DAEUMER	
	SUPPLY ENGINEERING DIVISION	<i>Sprague</i>	
	LOGISTICS ENGINEERING OFFICE	<i>Thom J. Michals</i>	
OCTOBER 1990			
U. S. ARMY DEFENSE AMMUNITION CENTER AND SCHOOL	CLASS	DIVISION	DRAWING
REVISION NO. 1	NOVEMBER 1995	19	48
SEE REVISION LISTING ON PAGE 2.		4145/15	FILE
			1-2-3-4- 14-22PM 1003

DO NOT SCALE

GENERAL NOTES

- A. THIS DOCUMENT HAS BEEN PREPARED AND ISSUED IN ACCORDANCE WITH AR 740-1 AND AUGMENTS TM 743-200-1 (CHAPTER 5).
- B. THE STORAGE PROCEDURES SPECIFIED HEREIN ARE APPLICABLE TO COMPLETE ROUNDS PACKED IN M18 SERIES CONTAINERS AND UNITIZED ON A 40" BY 48" WOODEN PALLETS.
- C. FOR DETAIL OF THE PALLET UNITS SEE PAGE 3. FOR UNITIZATION PROCEDURES SEE AMC DRAWING 19-48-4079/11-20PM1002.
- D. THE STORAGE PROCEDURES DEPICTED WITHIN THIS DOCUMENT ARE APPLICABLE FOR STORAGE IN VARIOUS TYPES AND SIZES OF MAGAZINES. THE STORAGE PROCEDURES DEPICTED FOR THE SPECIFIC TYPES OF MAGAZINES MAY ALSO BE UTILIZED TO STORE PALLET UNITS IN OTHER TYPES OF APPROVED MAGAZINES. MINOR ADJUSTMENTS MAY BE MADE TO FACILITATE STORAGE IN OTHER TYPES OF MAGAZINES, HOWEVER, THE BASIC PRINCIPLES AS DEPICTED HEREIN WILL BE FOLLOWED.
- E. **CAUTION:** THE ALLOWABLE "EXPLOSIVE LIMIT" ESTABLISHED FOR A MAGAZINE IS NOT TO BE EXCEEDED. THIS LIMITATION MAY REQUIRE A QUANTITY REDUCTION FROM THE STORAGE AS SHOWN.
- F. STORED PALLET UNITS MUST NOT CONTACT THE WALLS OF A MAGAZINE. TO PROVIDE FOR THIS MANDATORY CLEARANCE REQUIREMENT, UNITS MAY BE ELIMINATED FROM THE DEPICTED STORAGE PATTERN AS NECESSARY.
- G. AISLE DIMENSIONS SHOWN FOR STORAGE PROCEDURES IN MAGAZINES MAY BE ADJUSTED TO SUIT LOCAL CONDITIONS, VARIATIONS IN PALLET UNIT DIMENSIONS, AND/OR AVAILABLE MATERIALS HANDLING EQUIPMENT.
- H. THE MAXIMUM FLOOR LOAD FOR A MAGAZINE AS PRESCRIBED BY LOCAL STANDARDS WILL NOT BE EXCEEDED.
- J. IF AVAILABLE MHE PERMITS, ADDITIONAL PALLETIZED UNITS MAY BE STORED WITHIN THE MHE AREA AND/OR OTHER AVAILABLE AREA OF THE MAGAZINE.
- K. IF THE QUANTITY OF PALLET UNITS FOR A MAGAZINE IS TO BE REDUCED FROM WHAT IS SHOWN HEREIN DUE TO THE PERMITTED "EXPLOSIVE LIMIT" OR FOR ANY OTHER REASON, SUCH AS A LIMITED QUANTITY TO BE STORED, THE DELINEATED PROCEDURES ARE TO BE ADJUSTED BY OMITTING STACKS RATHER THAN BY OMITTING LAYERS.
- L. THE HEIGHT OF THE PACKAGE GUARD ON SOME FORKLIFT TRUCKS MAY NOT PERMIT PLACEMENT OF SOME TOP LAYER UNITS IN THE STACKS SHOWN IN THE STORAGE VIEWS HEREIN, UNLESS TWO UPPER PALLET UNITS ARE HANDLED AS ONE LIFT OR THE PACKAGE GUARD IS REMOVED (TINE CARRIAGE WILL IN MOST INSTANCES PROVIDE ADEQUATE PACKAGE GUARD PROTECTION). ONLY A FORKLIFT TRUCK OF ADEQUATE CAPACITY WILL BE USED WHEN LIFTING TWO PALLET UNITS AS ONE LIFT.
- M. STACK-STABILIZING DUNNAGE IN THE FORM OF "SHIMS MAY BE REQUIRED TO ACHIEVE SOUND AND ACCEPTABLE STABLE STACKS. SHIM MATERIAL OF VARYING THICKNESSES WILL BE USED AS REQUIRED TO GAIN LEVEL OR NEARLY LEVEL STACKS AND SOLID BEARING WITHIN A STACK FROM THE FLOOR OF A MAGAZINE TO THE TOP OF THE STACK.
- N. STORAGE OF MULTIPLE LOTS IN A MAGAZINE WILL REQUIRE CAREFUL PRE-PLANNING SO AS TO INSURE MHE ACCESSIBILITY TO ANY LOT IN ACCORDANCE WITH REQUIREMENTS SET FORTH IN THE APPLICABLE "SPECIAL NOTES" SECTIONS OF THE MULTIPLE LOT STORAGE PROCEDURES TYPICALLY SHOWN ON PAGES 28 THRU 36.
- O. ALTHOUGH SPECIFIC PROCEDURES ARE INCLUDED IN THIS DRAWING FOR STORING MULTIPLE LOTS WITHIN ONE STRUCTURE, THE BASIC STORAGE PATTERN AS SHOWN ON PAGES 4 THRU 27 CAN ALSO BE ADAPTED FOR THE STORING OF MORE THAN ONE LOT, HOWEVER, THE USE OF A STAGGERED LAYER STORAGE PATTERN AS SHOWN IS PROHIBITED. MULTIPLE LOTS OF PALLET UNITS WHEN STORED IN ACCORDANCE WITH THE BASIC STORAGE PATTERN MAY BE STORED WITH ONE OR MORE STACKS USED FOR EACH LOT. LOTS WILL NOT BE MIXED, EXCEPT TO THE EXTENT THAT UNITS OF ONE LOT WILL NOT BE STACKED ON TOP OF PALLET UNITS FROM ANOTHER LOT. MULTIPLE LOTS OF PALLET UNITS MAY BE STORED WITH ONE OR MORE ROWS USED FOR EACH LOT. (A ROW RUNS FROM THE REAR OF THE MAGAZINE TO THE FRONT). EACH LOT WITHIN THE MAGAZINE MUST BE ACCESSIBLE FOR REMOVAL AND INSPECTION/INVENTORY IN ACCORDANCE WITH OTHER CRITERIA SPECIFIED IN THESE GENERAL NOTES AND IN THE SPECIAL NOTES ON PAGES 28 THRU 36.

(CONTINUED AT RIGHT)

(GENERAL NOTES CONTINUED)

- P. ANY "LIGHT" PALLET UNIT THAT DOES NOT CONTAIN A FULL QUANTITY OF ROUNDS WILL NOT BE BURIED IN STORAGE. IT MUST BE POSITIONED ADJACENT TO AN AISLE, PREFERABLY IN FRONT OF THE LOT.
- O. A PRODUCTION OR STORAGE FACILITY IS AUTHORIZED TO HAVE ONE INCOMPLETE, UN-BANDED PARTIAL UNIT LOAD PER LOT IN A STORAGE STRUCTURE. PRIOR TO SHIPMENT OF A PARTIAL UNIT, A LAYER MUST BE COMPLETED, IF APPLICABLE, BY THE POSITIONING OF ONE OR MORE FILLERS AS DELINEATED BY DRAWING 19-48-4079/11-20PM1002. THE UNIT MUST THEN BE RE-BANDED WITH THE SAME SIZE AND QUANTITY OF STRAPS AS THE ORIGINAL UNIT.
- R. PORTIONS OF THE MAGAZINES, SUCH AS SIDEWALLS, END WALLS, AND ROOFS, HAVE NOT BEEN SHOWN IN THE STORAGE VIEWS FOR CLARITY PURPOSES.
- S. CONVERSION TO METRIC EQUIVALENTS: DIMENSIONS WITHIN THIS DOCUMENT ARE EXPRESSED IN INCHES, AND WEIGHTS ARE EXPRESSED IN POUNDS. WHEN NECESSARY, THE METRIC EQUIVALENT MAY BE COMPUTED ON THE BASIS OF ONE INCH EQUALS 25.4 MM, AND ONE POUND EQUALS 0.454 KG.
- T. WHEN LOCAL STORAGE CONDITIONS ARE SUCH THAT AN AMMUNITION STORAGE MAGAZINE NET EXPLOSIVE WEIGHT LIMIT WILL BE REACHED BEFORE ALL AVAILABLE STORAGE SPACE WILL BE UTILIZED, A COMBINATION OF THE VARIOUS STORAGE PATTERNS DELINEATED HEREIN MAY BE USED IN LIEU OF BLOCK STORAGE PATTERNS TO FACILITATE INVENTORY, INSPECTION, THE USE OF MATERIALS HANDLING EQUIPMENT, SURVEILLANCE, ETC., OF THE AMMUNITION TO BE STORED WITHIN THE MAGAZINE.


REVISIONS

REVISION NO. 1, DATED NOVEMBER 1995, CONSISTS OF:

- 1. CONVERTING TO CAD.


MATERIAL SPECIFICATIONS

LUMBER - - -: FED SPEC MM-L-751; DUNNAGE LUMBER, SEE TM 743 200-1.




PROTECTIVE COVER METHOD UNIT ●

CONTAINER - - - - - 50 EA @ 59 LBS (APPROX)
 CUBE - - - - - 60 CUBIC FEET (APPROX)
 GROSS WEIGHT - - - - - 3,504 LBS (APPROX)




FLAT DUNNAGE METHOD UNIT ⊕

CONTAINER - - - - - 50 EA @ 59 LBS (APPROX)
 CUBE - - - - - 65.6 CUBIC FEET (APPROX)
 GROSS WEIGHT - - - - - 3,179 LBS (APPROX)



ROUTED DUNNAGE METHOD UNIT ▲

CONTAINER - - - - - 50 EA @ 59 LBS (APPROX)
 CUBE - - - - - 62.3 CUBIC FEET (APPROX)
 GROSS WEIGHT - - - - - 3,192 LBS (APPROX)



STORAGE IN 81'-0" IGL00
(12'-9" HIGH)


PALLET UNIT	QUANTITY
●	225
▲	210
⊕	195

PLAN VIEW
(81'-0" IGL00)

* NOTE THAT THE QUANTITY OF PALLET UNITS IN THE "A" STACKS WILL DIFFER DEPENDENT UPON THE UNIT TO BE STORED.

SEE GENERAL NOTE "J" ON PAGE 2.


SEE GENERAL NOTE "F" ON PAGE 2.



SECTION A-A

("A" STACK, 14 PALLET UNITS) ● PROTECTIVE COVER METHOD UNIT

INDICATES OUTLINE OF DOOR OPENING.



SECTION B-B

("C" STACK, 5 PALLET UNITS)

STORAGE IN 60'-8" IGLOO

(12'-9" HIGH)


PALLET UNIT	QUANTITY
●	160
▲	150
⊕	140

*** STORAGE IN 40'-4" IGLOO**

(12'-9" HIGH)


PALLET UNIT	QUANTITY
●	99
▲	93
⊕	87

* 6 A-STACKS
3 C-STACKS




ISOMETRIC VIEW
(60'-8" IGLOO)


FOR "GENERAL NOTES" AND "MATERIAL SPECIFICATIONS",
SEE PAGE 2.



▲ ROUTED DUNNAGE METHOD UNIT
("A" STACK, 13 PALLET UNITS)




⊕ FLAT DUNNAGE METHOD UNIT
("A" STACK, 12 PALLET UNITS)



PLAN VIEW
(81'-2' MAGAZINE)

SEE GENERAL NOTE "J" ON PAGE 2.


SEE GENERAL NOTE "F" ON PAGE 2.



SECTION C-C

(*A* STACK, 11 PALLET UNITS) ● PROTECTIVE COVER METHOD UNIT

INDICATES OUTLINE OF DOOR OPENING.



SECTION D-D (*C* STACK, 5 PALLET UNITS)


STORAGE PROCEDURES IN 81'-2" L X 26'-6" W X 12'-1-3/4" H ARCH TYPE MAGAZINE

STORAGE IN 81'-2" MAGAZINE

(12'-1-3/4" HIGH)

PALLET UNIT **QUANTITY**


- ----- 180
- ▲ ----- 180
- ⊕ ----- 180



ISOMETRIC VIEW


(81'-2" MAGAZINE)

FOR "GENERAL NOTES" AND "MATERIAL SPECIFICATIONS",
SEE PAGE 2.



SECTION C-C 1

▲ **ROUTED DUNNAGE METHOD UNIT**
("A" STACK, 11 PALLET UNITS)




SECTION C-C 2

⊕ **FLAT DUNNAGE METHOD UNIT**
("A" STACK, 11 PALLET UNITS)

STORAGE PROCEDURES IN 81'-2" L X 26'-6" W X 12'-1-3/4" H ARCH TYPE MAGAZINE

***STORAGE IN 80'-0" MAGAZINE**
(12'-1-3/4" HIGH)




PALLET UNIT	QUANTITY
●	186
⊕	186
⊕	177

* FLAT DUNNAGE METHOD UNIT, (⊕), 18 "A" STACKS.

PLAN VIEW
(80'-0" MAGAZINE)

SEE GENERAL NOTE "J" ON PAGE 2.


SEE GENERAL NOTE "F" ON PAGE 2.



SECTION E-E

("A" STACK, 9 PALLET UNITS) ● PROTECTIVE COVER METHOD UNIT

INDICATES OUTLINE OF DOOR OPENING.



SECTION F-F ("C" STACK, 5 PALLET UNITS)

STORAGE PROCEDURES IN 80'-0" AND 40'-0" L X 25'-0" W X 12'-1-3/4" H ARCH TYPE MAGAZINES


***STORAGE IN 40'-0" MAGAZINE**

(12'-1-3/4" HIGH)

PALLET UNIT QUANTITY

●-----	87
▲-----	87
⊕-----	78


* FLAT DUNNAGE METHOD
UNIT, 7 "A" STACKS.




SEE GENERAL NOTE
"J" ON PAGE 2.

ISOMETRIC VIEW
(40'-0" MAGAZINE)

**FOR "GENERAL NOTES" AND "MATERIAL SPECIFICATIONS",
SEE PAGE 2.**



SECTION E-E 1
▲ **ROUTED DUNNAGE METHOD UNIT**
("A" STACK, 9 PALLET UNITS)




SECTION E-E 2
⊕ **FLAT DUNNAGE METHOD UNIT**
("A" STACK, 9 PALLET UNITS)

STORAGE IN 80'-0" MAGAZINE

(11'-0" HIGH)

PALLET UNIT	QUANTITY
●	162
▲	162
⊕	162




PLAN VIEW

(80'-0" MAGAZINE)

SEE GENERAL NOTE "J" ON PAGE 2.


SEE GENERAL NOTE "F" ON PAGE 2.



SECTION G-G

("A" STACK, 10 PALLET UNITS) ● PROTECTIVE COVER METHOD UNIT

INDICATES OUTLINE OF DOOR OPENING.




SECTION H-H

("C" STACK, 4 PALLET UNITS)

STORAGE IN 40'-0" MAGAZINE

(11'-0" HIGH)


PALLET UNIT	QUANTITY
●	72
▲	72
⊕	72




SEE GENERAL NOTE "J" ON PAGE 2.

ISOMETRIC VIEW
(40'-0" MAGAZINE)

FOR "GENERAL NOTES" AND "MATERIAL SPECIFICATIONS", SEE PAGE 2.



▲ ROUTED DUNNAGE METHOD UNIT
("A" STACK, 10 PALLET UNITS)




⊕ FLAT DUNNAGE METHOD UNIT
("A" STACK, 10 PALLET UNITS)

STORAGE IN 80'-0" MAGAZINE

(10'-0" HIGH)


PALLET UNIT	QUANTITY
●	147
▲	147
⊕	132



PLAN VIEW
(80'-0" MAGAZINE)

SEE GENERAL NOTE "J" ON PAGE 2.


SEE GENERAL NOTE "F" ON PAGE 2.



SECTION J-J

("A" STACK, 9 PALLET UNITS) ● PROTECTIVE COVER METHOD UNIT

INDICATES OUTLINE OF DOOR OPENING.



SECTION K-K


("C" STACK, 4 PALLET UNITS)

STORAGE IN 40'-0" MAGAZINE

(10'-0" HIGH)

PALLET UNIT QUANTITY


●	-----	66
▲	-----	66
⊕	-----	60




SEE GENERAL NOTE "J" ON PAGE 2.

ISOMETRIC VIEW
(40'-0" MAGAZINE)


FOR "GENERAL NOTES" AND "MATERIAL SPECIFICATIONS", SEE PAGE 2.



▲ ROUTED DUNNAGE METHOD UNIT
("A" STACK, 9 PALLET UNITS)



⊕ FLAT DUNNAGE METHOD UNIT
("A" STACK, 8 PALLET UNITS)



STORAGE IN STRADLEY MAGAZINE


(14'-0" HIGH)

PALLET UNIT	QUANTITY
●	292
▲	273 --- (19 "A" STACKS) (3 "C" STACKS)
⊕	260 --- (18 "A" STACKS) (3 "C" STACKS)

STORAGE IN 89'-0" OVAL ARCH MAGAZINE


(14'-4" HIGH)

PALLET UNIT	QUANTITY
●	334 --- (22 "A" STACKS) (3 "C" STACKS)
▲	312 --- (22 "A" STACKS) (3 "C" STACKS)
⊕	290 --- (21 "A" STACKS) (2 "C" STACKS)




ISOMETRIC VIEW
(STRADLEY MAGAZINE)

FOR "GENERAL NOTES" AND "MATERIAL SPECIFICATIONS",
SEE PAGE 2.




▲ ROUTED DUNNAGE METHOD UNIT
("A" STACK, 13 PALLET UNITS)



⊕ FLAT DUNNAGE METHOD UNIT
("A" STACK, 13 PALLET UNITS)

**STORAGE PROCEDURES IN 80'-0" L X 25'-0" W X 14'-0" H STRADLEY AND
89'-0" L X 24'-10" W X 14'-4" H OVAL ARCH MAGAZINES**




STORAGE IN 89'-0" STEEL ARCH MAGAZINE

(13'-6" HIGH)


PALLET UNIT **QUANTITY**

- ----- 261
- ▲ ----- 261 --- (22 "A" STACKS, 2 "C" STACKS)
- ⊕ ----- 250 --- (21 "A" STACKS, 2 "C" STACKS)




ISOMETRIC VIEW
(STEEL ARCH MAGAZINE)

FOR "GENERAL NOTES" AND "MATERIAL SPECIFICATIONS",
SEE PAGE 2.



SECTION N-N 1
▲ **ROUTED DUNNAGE METHOD UNIT**
("A" STACK, 11 PALLET UNITS)



SECTION N-N 2
⊕ **FLAT DUNNAGE METHOD UNIT**
("A" STACK, 11 PALLET UNITS)

STORAGE PROCEDURES IN 89'-0" L X 24'-11" W X 13'-6" H STEEL ARCH MAGAZINE

STORAGE IN 44'-7" DIA MAGAZINE


STORAGE IN 52'-0" DIA MAGAZINE

PALLET UNIT	QUANTITY
●	130
▲	130
⊕	124

PALLET UNIT	QUANTITY
●	196
▲	196
⊕	190

ARROWS INDICATE DIRECTION OF STORAGE FROM WALLS TOWARD CENTER OF MAGAZINE.


DOTTED LINE REPRESENTS OUT LINE OF 44'-7" DIA MAGAZINE.




UNCIRCLED NUMBERS INDICATE THE LAYERS HIGH THAT PALLET UNITS ARE STACKED IN A 52'-0" DIA MAGAZINE. CIRCLED NUMBERS INDICATE THE LAYERS HIGH THAT PALLET UNITS ARE STACKED IN A 44'-7" DIA MAGAZINE.

SEE GENERAL NOTE "J" ON PAGE 2.

PLAN VIEW




SECTION P-P




SECTION O-O

FOR "GENERAL NOTES" AND "MATERIAL SPECIFICATIONS", SEE PAGE 2.




ARROWS INDICATE DIRECTION OF STORAGE FROM REAR WALL TOWARD DOORS OR FROM SIDE WALLS OR CENTER OF MAGAZINE TOWARD MHE AISLE.

PALLET UNITS IN TOP LAYER WILL BE OMITTED AS REQUIRED TO CLEAR ROOF SUPPORT CAPS AT TOP OF COLUMNS.



STORAGE IN 100'-8" X 50'-0" MAGAZINE

<u>PALLET UNIT</u>	<u>QUANTITY</u>
●	762
▲	762
⊕	762





ISOMETRIC VIEW
(100'-8" X 50'-0" MAGAZINE)

SPECIAL NOTE:


1. IF THE QUANTITY FOR A MAGAZINE IS TO BE REDUCED FROM WHAT IS SHOWN DUE TO THE PERMITTED "EXPLOSIVE LIMIT" OR FOR ANY OTHER REASON, SUCH AS A LIMITED QUANTITY TO BE STORED, THE DELINEATED PROCEDURES ARE TO BE ADJUSTED BY OMITTING STACKS RATHER THAN BY OMITTING LAYERS.

FOR "GENERAL NOTES" AND "MATERIAL SPECIFICATIONS",
SEE PAGE 2.






STORAGE IN TYPE II BUNKER

<u>PALLET UNIT</u>	<u>QUANTITY</u>
●	420
▲	418
⊕	380




ISOMETRIC VIEW

FOR "GENERAL NOTES" AND "MATERIAL SPECIFICATIONS",
SEE PAGE 2.



STORAGE IN TYPE III BUNKER


<u>PALLET UNIT</u>	<u>QUANTITY</u>
●	272
▲	272
⊕	242



ISOMETRIC VIEW

(PROTECTIVE COVER/ROUTED DUNNAGE METHOD UNITS)


FOR "GENERAL NOTES" AND "MATERIAL SPECIFICATIONS",
SEE PAGE 2.




PLAN VIEW

⊕ FLAT DUNNAGE METHOD UNIT.


STORAGE PROCEDURES IN 60'-0" L X 40'-0" W X 11'-0" H TYPE III BUNKER



NOTE: FOR MULTIPLE-LOT STORAGE, PALLET UNITS WILL BE POSITIONED IN THE MAGAZINE AS DEPICTED IN THE "PLAN VIEW" ON PAGE 35. FOR THE DEPICTED MAGAZINE, PALLET UNITS CAN BE POSITIONED TWO (2) DEEP ON ONE SIDE OF THE MAGAZINE OR ONE (1) ON EACH SIDE OF THE MAGAZINE. IN EITHER CASE ONE OR MORE LOTS (NOT TO EXCEED 12 LIFTS) CAN BE STORED AT THE REAR OF THE MAGAZINE AS SHOWN ON PAGE 35. HOWEVER, COMPLIANCE WITH ALL OF THE MULTIPLE-LOT CRITERIA SPECIFIED IN THE "SPECIAL NOTES" ON PAGE 35 MUST BE OBSERVED.




INDICATES OUTLINE OF DOOR OPENING.




STORAGE IN TYPE IV BUNKER

<u>PALLET UNIT</u>	<u>QUANTITY</u>
●	80
▲	80
⊕	72



ISOMETRIC VIEW

FOR "GENERAL NOTES" AND "MATERIAL SPECIFICATIONS",
SEE PAGE 2.




PLAN VIEW
(81'-0" IGLOO SHOWN)

ARROWS INDICATE DIRECTION OF STORAGE FROM FRONT AND/OR REAR TOWARD CENTER OF THE LENGTH OF THE MAGAZINE.

INDICATES OUTLINE OF DOOR OPENING.

SEE GENERAL NOTE "F" ON PAGE 2.





SECTION X-X

SPECIAL NOTES:

(SPECIAL NOTES CONTINUED)

1. THE STORAGE PLANS AND CONFIGURATIONS SHOWN ON THIS PAGE ARE TYPICAL ONLY AND APPLY TO RELATIVELY LARGE LOTS. ADAPTATIONS MAY BE MADE AS NUMBER AND SIZES OF LOTS TO BE STORED IN MAGAZINE REQUIRE.
2. AN INSPECTION/INVENTORY AISLE MUST BE PROVIDED AT ONE SIDE OR END OF EACH LOT.
3. GENERALLY, THE LARGEST LOT SHOULD BE STORED IN THE REAR OF THE MAGAZINE. HOWEVER, THE REAR AREA MAY BE USED TO STORE MORE THAN ONE LOT BY ERECTING ROWS SIMILAR TO THOSE SHOWN IN THE FRONTAL AREA. A CENTER AISLE WILL NOT BE REQUIRED IN THE REAR AREA AS LONG AS EACH LOT IS ACCESSIBLE FOR REMOVAL AND INSPECTION/INVENTORY IN ACCORDANCE WITH OTHER CRITERIA SPECIFIED IN THESE SPECIAL NOTES AND IN THE GENERAL NOTES ON PAGE 2.
4. EACH LOT WITHIN THE MAGAZINE MUST BE ACCESSIBLE FOR MOVEMENT BY MHE. A SINGLE-LOT OF PALLET UNITS IS CONSIDERED "ACCESSIBLE" IF NO MORE THAN TWELVE (12) "LIFTS" OF ANOTHER LOT OR LOTS HAVE TO BE MADE TO GAIN ACCESS TO THAT LOT. A "LIFT" MAY CONSIST OF ONE (1) OR MORE PALLET UNITS, PROVIDING THE CAPACITY OF MHE PERMITS, AND SAFE HANDLING IS NOT JEOPARDIZED.
5. FOR STORAGE OF MULTIPLE LOTS, THE DISTANCE FROM THE SIDEWALL WILL BE BASED ON THE OVERHEAD CLEARANCE REQUIRED FOR MHE.
6. WHEN TWO LOTS ARE STORED ADJACENT TO EACH OTHER, THEY SHOULD BE SEPARATED BY AT LEAST 1" TO PROVIDE CLEARANCE FOR REMOVAL OF EITHER LOT.
7. A 14'-3" MHE OPERATING AREA HAS BEEN SHOWN. THE MHE OPERATING AREA CAN BE ENLARGED AS REQUIRED TO SUIT AVAILABLE FORKLIFT TRUCKS, AND SHOULD BE MADE SMALLER IF AVAILABLE MHE PERMITS. A "CENTER AISLE" (SPACE BETWEEN STORAGE ON EACH SIDE OF MAGAZINE) IS TO BE AT LEAST 48 INCHES WIDE. AN AISLE SLIGHTLY WIDER THAN 48 INCHES WILL ENHANCE FORKLIFT TRUCK MOVEMENT WITHIN A MAGAZINE; HOWEVER, THIS AISLE SHOULD NOT BE MADE WIDER IF A LOSS OF STORAGE RESULTS.

(CONTINUED AT RIGHT)




SPECIAL NOTES:

(SPECIAL NOTES CONTINUED)

1. THE STORAGE PLANS AND CONFIGURATIONS SHOWN ON THIS PAGE ARE TYPICAL ONLY AND APPLY TO STORAGE OF NUMEROUS SMALL LOTS. ADAPTATIONS MAY BE MADE AS NUMBER AND SIZES OF LOTS TO BE STORED IN MAGAZINE REQUIRE.
2. AN INSPECTION/INVENTORY AISLE NOT LESS THAN 18" WIDE MUST BE PROVIDED AT ONE SIDE OF EACH LOT.
3. GENERALLY, THE LARGEST LOT SHOULD BE STORED IN THE REAR OF THE MAGAZINE. HOWEVER, THE REAR AREA MAY BE USED TO STORE MORE THAN ONE LOT BY ERECTING STACKS SIMILAR TO THOSE SHOWN IN THE FRONTAL AREA. AN MHE AISLE WILL BE REQUIRED ON ONE SIDE OF THE MAGAZINE, AND EACH LOT MUST BE ACCESSIBLE FOR REMOVAL AND INSPECTION/INVENTORY IN ACCORDANCE WITH OTHER CRITERIA SPECIFIED IN THESE SPECIAL NOTES AND IN THE GENERAL NOTES ON PAGE 2.
4. A MIXED-LOT PALLET UNIT MAY HAVE FROM TWO LOTS PER PALLET UNIT UPWARDS TO AS MANY DIFFERENT LOTS AS COMPLETE ROUNDS WITHIN THAT UNIT. HOWEVER, ALL COMPLETE ROUNDS AND LOTS WITHIN THE PALLET UNIT MUST HAVE THE SAME NATIONAL STOCK NUMBER AND CONDITION CODE.
5. EACH LOT WITHIN THE MAGAZINE MUST BE ACCESSIBLE FOR MOVEMENT BY MHE. PALLET UNITS OF A SINGLE-LOT OR MIXED-LOT PALLET UNITS ARE CONSIDERED "ACCESSIBLE" IF NO MORE THAN TWELVE (12) "LIFTS" OF ANOTHER LOT OR LOTS HAVE TO BE MADE TO GAIN ACCESS TO THE SINGLE-LOT OR MIXED-LOT UNITS. A "LIFT" MAY CONSIST OF ONE (1) OR MORE PALLET UNITS, PROVIDING THE CAPACITY OF THE MHE PERMITS, AND SAFE HANDLING IS NOT JEOPARDIZED.
6. FOR STORAGE OF MULTIPLE LOTS, THE DISTANCE FROM THE SIDEWALL WILL BE BASED ON THE OVERHEAD CLEARANCE REQUIRED FOR MHE.
7. WHEN TWO LOTS ARE STORED ADJACENT TO EACH OTHER, THEY SHOULD BE SEPARATED BY AT LEAST 1" TO PROVIDE CLEARANCE FOR REMOVAL OF EITHER LOT.
8. AREAS INCLUDED BY DOTTED LINES INDICATE LOCATIONS WHERE ADDITIONAL LOTS MAY BE STORED OR WHERE ADDITIONAL ITEMS MAY BE STORED, THAT ARE FROM THE LOT OR LOTS WHICH ARE DIRECTLY OR ALMOST DIRECTLY ACROSS THE CENTER AISLE ON THE OTHER SIDE OF THE MAGAZINE. COMPLIANCE WITH ALL OF THE MULTIPLE-LOT CRITERIA AS SET FORTH ON THIS PAGE MUST BE OBSERVED. THE SIZE OF THE LOTS BEING STORED AND THE CRITERIA OF SPECIAL NOTE 5, RELATIVE TO "12 LIFTS", WILL BE MAJOR FACTORS IMPACTING ON THE NUMBER OF PALLET UNITS THAT CAN BE STORED IN AN "ADDITIONAL STORAGE LOCATION" MORE OR FEWER STACKS THAN SHOWN MAY BE STORED AT ANY ONE OF THE ADDITIONAL STORAGE LOCATIONS. A 12'-0" MHE OPERATING AREA HAS BEEN SPECIFIED FOR ACCESS TO EACH "ADDITIONAL LOCATION" BY FORKLIFT TRUCK. THE MHE OPERATING AREA CAN BE ENLARGED AS REQUIRED TO SUIT AVAILABLE FORKLIFT TRUCKS, AND SHOULD BE MADE SMALLER IF AVAILABLE MHE PERMITS. A "CENTER AISLE" (SPACE BETWEEN STORAGE ON ONE SIDE OF A MAGAZINE AND AN "ADDITIONAL STORAGE LOCATION") IS TO BE AT LEAST 48 INCHES WIDE. AN AISLE SLIGHTLY WIDER THAN 48 INCHES WILL ENHANCE FORKLIFT TRUCK MOVEMENT WITHIN A MAGAZINE, HOWEVER, THIS AISLE SHOULD NOT BE MADE WIDER IF A LOSS IN STORAGE RESULTS.

(CONTINUED AT RIGHT)


TYPICAL MULTIPLE-LOT STORAGE IN IGLOO AND ARCH TYPE MAGAZINES



PLAN VIEW
(STRADLEY MAGAZINE)

SEE GENERAL NOTE "F" ON PAGE 2.

INDICATES OUTLINE OF DOOR OPENING.



SECTION Z-Z


SPECIAL NOTES:

1. THE STORAGE PLANS AND CONFIGURATIONS SHOWN ON THIS PAGE ARE TYPICAL ONLY AND APPLY TO RELATIVELY LARGE LOTS. ADAPTATIONS MAY BE MADE AS NUMBER AND SIZES OF LOTS TO BE STORED IN MAGAZINE REQUIRE.
2. GENERALLY, THE LARGEST LOT SHOULD BE STORED IN THE REAR OF THE MAGAZINE. HOWEVER, THE AREA MAY BE USED TO STORE MORE THAN ONE LOT BY ERECTING ROWS SIMILAR TO THOSE SHOWN IN THE FRONTAL AREA. A CENTER AISLE WILL NOT BE REQUIRED IN THE REAR AREA AS LONG AS EACH LOT IS ACCESSIBLE FOR REMOVAL AND INSPECTION/INVENTORY IN ACCORDANCE WITH OTHER CRITERIA SPECIFIED IN THESE SPECIAL NOTES AND IN THE GENERAL NOTES ON PAGE 2.
3. EACH LOT WITHIN THE MAGAZINE MUST BE ACCESSIBLE FOR MOVEMENT BY MHE. A SINGLE-LOT OF PALLET UNITS IS CONSIDERED "ACCESSIBLE" IF NO MORE THAN TWELVE (12) "LIFTS" OF ANOTHER LOT OR LOTS HAVE TO BE MADE TO GAIN ACCESS TO THAT LOT. A "LIFT" MAY CONSIST OF ONE (1) OR MORE PALLET UNITS, PROVIDING THE CAPACITY OF MHE PERMITS, AND SAFE HANDLING IS NOT JEOPARDIZED.

(SPECIAL NOTES CONTINUED)

4. FOR STORAGE OF MULTIPLE LOTS, THE DISTANCE FROM THE SIDEWALL WILL BE BASED ON THE OVERHEAD CLEARANCE REQUIRED FOR MHE.
5. WHEN TWO LOTS ARE STORED ADJACENT TO EACH OTHER, THEY SHOULD BE SEPARATED BY AT LEAST 1" TO PROVIDE CLEARANCE FOR REMOVAL OF EITHER LOT.
6. AN INSPECTION/INVENTORY AISLE MUST BE PROVIDED AT ONE SIDE OR END OF EACH LOT.
7. A 13'-3" MHE OPERATING AREA HAS BEEN SHOWN. THE MHE OPERATING AREA CAN BE ENLARGED AS REQUIRED TO SUIT AVAILABLE FORKLIFT TRUCKS, AND SHOULD BE MADE SMALLER IF AVAILABLE MHE PERMITS. A "CENTER AISLE" (SPACE BETWEEN STORAGE ON EACH SIDE OF MAGAZINE) IS TO BE AT LEAST 60 INCHES WIDE. AN AISLE SLIGHTLY WIDER THAN 60 INCHES WILL ENHANCE FORKLIFT TRUCK MOVEMENT WITHIN A MAGAZINE, HOWEVER, THIS AISLE SHOULD NOT BE MADE WIDER IF A LOSS OF STORAGE RESULTS.

(CONTINUED AT RIGHT)




SPECIAL NOTES:


1. THE STORAGE PLANS AND CONFIGURATIONS SHOWN ON THIS PAGE ARE TYPICAL ONLY AND APPLY TO STORAGE OF NUMEROUS SMALL LOTS. ADAPTATIONS MAY BE MADE AS NUMBER AND SIZES OF LOTS TO BE STORED IN MAGAZINE REQUIRE.
2. AN INSPECTION/INVENTORY AISLE NOT LESS THAN 18" WIDE MUST BE PROVIDED AT ONE SIDE OF EACH LOT.
3. GENERALLY, THE LARGEST LOT SHOULD BE STORED IN THE REAR OF THE MAGAZINE. HOWEVER, THE REAR AREA MAY BE USED TO STORE MORE THAN ONE LOT BY ERECTING STACKS SIMILAR TO THOSE SHOWN IN THE FRONTAL AREA. AN MHE AISLE WILL BE REQUIRED ON ONE SIDE OF THE MAGAZINE, AND EACH LOT MUST BE ACCESSIBLE FOR REMOVAL AND INSPECTION/INVENTORY IN ACCORDANCE WITH OTHER CRITERIA SPECIFIED IN THESE SPECIAL NOTES AND IN THE GENERAL NOTES ON PAGE 2.
4. A MIXED-LOT PALLET UNIT MAY HAVE FROM TWO LOTS PER PALLET UNIT UPWARDS TO AS MANY DIFFERENT LOTS AS COMPLETE ROUNDS WITHIN THAT UNIT. HOWEVER, ALL COMPLETE ROUNDS AND LOTS WITHIN THE PALLET UNIT MUST HAVE THE SAME NATIONAL STOCK NUMBER AND CONDITION CODE.
5. EACH LOT WITHIN THE MAGAZINE MUST BE ACCESSIBLE FOR MOVEMENT BY MHE. PALLET UNITS OF A SINGLE-LOT OR MIXED-LOT PALLET UNITS ARE CONSIDERED "ACCESSIBLE" IF NO MORE THAN TWELVE (12) "LIFTS" OF ANOTHER LOT OR LOTS HAVE TO BE MADE TO GAIN ACCESS TO THE SINGLE-LOT OR MIXED-LOT UNITS. A "LIFT" MAY CONSIST OF ONE (1) OR MORE PALLET UNITS, PROVIDING THE CAPACITY OF THE MHE PERMITS, AND SAFE HANDLING IS NOT JEOPARDIZED.

(CONTINUED AT RIGHT)

(SPECIAL NOTES CONTINUED)

6. FOR STORAGE OF MULTIPLE LOTS, THE DISTANCE FROM THE SIDEWALL WILL BE BASED ON THE OVERHEAD CLEARANCE REQUIRED FOR MHE.
7. WHEN TWO LOTS ARE STORED ADJACENT TO EACH OTHER, THEY SHOULD BE SEPARATED BY AT LEAST 1" TO PROVIDE CLEARANCE FOR REMOVAL OF EITHER LOT.
8. AREAS ENCLOSED BY DOTTED LINES INDICATE LOCATIONS WHERE ADDITIONAL LOTS MAY BE STORED OR WHERE ADDITIONAL ITEMS MAY BE STORED, THAT ARE FROM THE LOT OR LOTS WHICH ARE DIRECTLY OR ALMOST DIRECTLY ACROSS THE CENTER AISLE ON THE OTHER SIDE OF THE MAGAZINE. COMPLIANCE WITH ALL OF THE MULTIPLE-LOT CRITERIA AS SET FORTH ON THIS PAGE MUST BE OBSERVED. THE SIZE OF THE LOTS BEING STORED AND THE CRITERIA OF SPECIAL NOTE 5, RELATIVE TO "12 LIFTS", WILL BE MAJOR FACTORS IMPACTING ON THE NUMBER OF PALLET UNITS THAT CAN BE STORED IN AN "ADDITIONAL STORAGE LOCATION" MORE OR FEWER STACKS THAN SHOWN MAY BE STORED AT ANY ONE OF THE ADDITIONAL STORAGE LOCATIONS. A 13'-0" MHE OPERATING AREA HAS BEEN SPECIFIED FOR ACCESS TO EACH "ADDITIONAL LOCATION" BY FORKLIFT TRUCK. THE MHE OPERATING AREA CAN BE ENLARGED AS REQUIRED TO SUIT AVAILABLE FORKLIFT TRUCKS, AND SHOULD BE MADE SMALLER IF AVAILABLE MHE PERMITS. A "CENTER AISLE" (SPACE BETWEEN STORAGE ON ONE SIDE OF A MAGAZINE AND AN "ADDITIONAL STORAGE LOCATION") IS TO BE AT LEAST 60 INCHES WIDE. AN AISLE SLIGHTLY WIDER THAN 60 INCHES WILL ENHANCE FORKLIFT TRUCK MOVEMENT WITHIN A MAGAZINE, HOWEVER, THIS AISLE SHOULD NOT BE MADE WIDER IF A LOSS IN STORAGE RESULTS.







SECTION BB-BB

SPECIAL NOTES:

1. THE STORAGE PLANS SHOWN ARE TYPICAL ONLY. ADAPTATIONS MAY BE MADE AS NUMBER AND SIZES OF LOTS TO BE STORED IN MAGAZINE REQUIRE.
2. AN INSPECTION/INVENTORY AISLE NOT LESS THAN 18" WIDE MUST BE PROVIDED AT ONE SIDE OF EACH LOT.
3. GENERALLY, THE LARGEST LOT SHOULD BE STORED ON ONE SIDE OF THE MAGAZINE. HOWEVER, BOTH SIDES MAY BE USED TO STORE MORE THAN ONE LOT BY ERECTING ROWS SIMILAR TO THOSE SHOWN ON THE LEFT SIDE. EACH ADDITIONAL LOT MUST BE ACCESSIBLE FOR REMOVAL AND INSPECTION/INVENTORY IN ACCORDANCE WITH OTHER CRITERIA SPECIFIED IN THESE SPECIAL NOTES AND IN THE GENERAL NOTES ON PAGE 2.
4. A MIXED-LOT PALLET UNIT MAY HAVE TWO LOTS PER PALLET UNIT UPWARDS TO AS MANY DIFFERENT LOTS AS COMPLETE ROUNDS WITHIN THE PALLET UNIT. HOWEVER, ALL COMPLETE ROUNDS AND LOTS WITHIN THE PALLET UNIT MUST HAVE THE SAME NATIONAL STOCK NUMBER AND CONDITION CODE.
5. EACH LOT WITHIN THE MAGAZINE MUST BE ACCESSIBLE FOR MOVEMENT BY MHE. PALLET UNITS OF A SINGLE-LOT OR MIXED LOT PALLET UNITS ARE CONSIDERED "ACCESSIBLE" IF NO MORE THAN TWELVE (12) "LIFTS" OF ANOTHER LOT OR LOTS HAVE TO BE MADE TO GAIN ACCESS TO THE SINGLE-LOT OR MIXED-LOT UNITS. A "LIFT" MAY CONSIST OF ONE (1) OR MORE PALLET UNITS, PROVIDING THE CAPACITY OF MHE PERMITS, AND SAFE HANDLING IS NOT JEOPARDIZED.
6. FOR STORAGE OF MULTIPLE LOTS, THE DISTANCE FROM THE WALL WILL BE BASED ON THE OVERHEAD CLEARANCE REQUIRED FOR MHE.
7. WHEN TWO LOTS ARE STORED ADJACENT TO EACH OTHER THEY SHOULD BE SEPARATED BY AT LEAST 1" TO PROVIDE CLEARANCE FOR REMOVAL OF EITHER LOT.
8. AREAS INCLOSED BY DOTTED LINES INDICATE LOCATIONS WHERE ADDITIONAL LOTS MAY BE STORED OR WHERE ADDITIONAL ITEMS MAY BE STORED, THAT ARE FROM THE LOT OR LOTS ADJACENT TO THE MHE AISLE. COMPLIANCE WITH ALL OF THE MULTIPLE LOT CRITERIA AS SET FORTH ON THIS PAGE MUST BE OBSERVED. THE SIZE OF THE LOTS BEING STORED AND THE CRITERIA OF SPECIAL NOTE 5. RELATIVE TO "12" LIFTS WILL BE MAJOR FACTORS IMPACTING ON THE NUMBER OF PALLET UNITS THAT CAN BE STORED IN AN "ADDITIONAL STORAGE LOCATION". MORE OR FEWER STACKS THAN SHOWN MAY BE STORED AT ANY ONE OF THE ADDITIONAL STORAGE LOCATIONS. AN 11'-6" MHE OPERATING AREA HAS BEEN SPECIFIED FOR ACCESS TO EACH "ADDITIONAL LOCATION" BY FORKLIFT TRUCK. THIS OPERATING AREA IS BASED ON REQUIREMENTS OF FORKLIFT TRUCKS COMMONLY USED IN STORAGE MAGAZINES. THE MHE OPERATING AREA CAN BE ENLARGED AS REQUIRED TO SUIT AVAILABLE FORKLIFT TRUCKS, AND SHOULD BE MADE SMALLER IF AVAILABLE MHE PERMITS. A "CENTER AISLE" (SPACE BETWEEN STORAGE ON ONE SIDE OF THE MAGAZINE AND AN "ADDITIONAL STORAGE LOCATION") IS TO BE AT LEAST 60 INCHES WIDE. AN AISLE SLIGHTLY WIDER THAN 60 INCHES WILL ENHANCE FORKLIFT TRUCK MOVEMENT WITHIN A MAGAZINE; HOWEVER, THIS AISLE SHOULD NOT BE MADE WIDER IF A LOSS IN STORAGE RESULTS.



SPECIAL NOTES:


1. THE STORAGE PLANS AND CONFIGURATIONS SHOWN ON THIS PAGE ARE TYPICAL ONLY. ADAPTATIONS MAY BE MADE AS NUMBER AND SIZES OF LOTS TO BE STORED IN MAGAZINE REQUIRE.
2. GENERALLY, THE LARGEST LOT SHOULD BE STORED IN THE REAR OR ON ONE SIDE OF THE MAGAZINE, HOWEVER, THESE AREAS MAY BE USED TO STORE MORE THAN ONE LOT BY ERECTING ROWS SIMILAR TO THOSE SHOWN IN THE SMALLER SIZED LOTS, OR AS TYPICALLY SHOWN BY DOTTED LINES. EACH ADDITIONAL LOT MUST BE ACCESSIBLE FOR REMOVAL AND INSPECTION/INVENTORY IN ACCORDANCE WITH OTHER CRITERIA SPECIFIED IN THESE SPECIAL NOTES AND IN THE GENERAL NOTES ON PAGE 2.
3. A MIXED LOT PALLET UNIT MAY HAVE FROM TWO LOTS PER PALLET UNIT UPWARDS TO AS MANY DIFFERENT LOTS AS COMPLETE ROUNDS WITHIN THAT UNIT, HOWEVER, ALL COMPLETE ROUNDS AND LOTS WITHIN THE PALLET MUST HAVE THE SAME NATIONAL STOCK NUMBER AND CONDITION CODE.
4. WHEN TWO LOTS ARE STORED ADJACENT TO EACH OTHER, THEY SHOULD BE SEPARATED BY AT LEAST 1" TO PROVIDE CLEARANCE FOR REMOVAL OF EITHER LOT.

(SPECIAL NOTES CONTINUED)

5. AN INSPECTION/INVENTORY AISLE NOT LESS THAN 18" WIDE MUST BE PROVIDED AT ONE SIDE OF EACH LOT.
6. EACH LOT WITHIN THE MAGAZINE MUST BE ACCESSIBLE FOR MOVEMENT BY MHE. PALLET UNITS OF A SINGLE LOT ARE CONSIDERED "ACCESSIBLE" IF NO MORE THAN TWENTY FOUR (24) "LIFTS" OF ANOTHER LOT OR LOTS HAVE TO BE MADE TO GAIN ACCESS TO THE SINGLE LOT.
7. THE MHE AISLE MAY BE USED TO STORE ADDITIONAL LOTS, OR ADDITIONAL ITEMS THAT ARE FROM A LOT OR LOTS ADJACENT TO THE MHE AISLE, AS SHOWN IN THE AREAS INCLOSED BY DOTTED LINES. ADEQUATE SPACE FOR MHE OPERATION MUST BE AVAILABLE FOR THE ADDITIONAL STORAGE. ALSO, COMPLIANCE WITH ALL OF THE MULTIPLE LOT CRITERIA AS SET FORTH ON THIS PAGE, MUST BE OBSERVED.


(CONTINUED AT RIGHT)

TYPICAL MULTIPLE-LOT STORAGE IN 100'-8" L X 50'-0" W RECTANGULAR MAGAZINE



MIXED LOT PALLET UNITS. SEE SPECIAL NOTE 4 BELOW.

PLAN VIEW





SECTION DD-DD

SPECIAL NOTES:

(SPECIAL NOTES CONTINUED)

1. THE STORAGE PLANS AND CONFIGURATIONS SHOWN ON THIS PAGE ARE TYPICAL ONLY. ADAPTATIONS MAY BE MADE AS NUMBER AND SIZES OF LOTS TO BE STORED IN BUNKER REQUIRE.
2. AN INSPECTION/INVENTORY AISLE NOT LESS THAN 18" WIDE MUST BE PROVIDED AT ONE SIDE OR END OF EACH LOT.
3. EACH LOT WITHIN THE BUNKER MUST BE ACCESSIBLE FOR MOVEMENT BY MHE. PALLET UNITS OF A SINGLE-LOT ARE CONSIDERED "ACCESSIBLE" IF NO MORE THAN TWELVE (12) "LIFTS" OF ANOTHER LOT OR LOTS HAVE TO BE MADE TO GAIN ACCESS TO THE SINGLE-LOT.
4. MIXED LOT PALLET UNIT MAY HAVE FROM TWO LOTS PER PALLET UNIT UPWARDS TO AS MANY DIFFERENT LOTS AS COMPLETE ROUNDS WITHIN THAT UNIT. HOWEVER, ALL COMPLETE ROUNDS AND LOTS WITHIN THE PALLET UNIT MUST HAVE THE SAME NATIONAL STOCK NUMBER AND CONDITION CODE.
5. WHEN TWO LOTS ARE STORED ADJACENT TO EACH OTHER, THEY SHOULD BE SEPARATED BY AT LEAST 1" TO PROVIDE CLEARANCE FOR REMOVAL OF EITHER LOT.
6. THE MHE AISLE MAY BE USED TO STORE ADDITIONAL LOTS, OR ADDITIONAL ITEMS THAT ARE FROM A LOT OR LOTS ADJACENT TO THE MHE AISLE, AS SHOWN IN THE AREA ENCLOSED BY DOTTED LINES. ADEQUATE SPACE FOR MHE OPERATION MUST BE AVAILABLE FOR THE ADDITIONAL STORAGE. ALSO, COMPLIANCE WITH ALL OF THE MULTIPLE-LOT CRITERIA AS SET FORTH ON THIS PAGE MUST BE OBSERVED.

(CONTINUED AT RIGHT)



SPECIAL NOTES:

1. THE STORAGE PLANS AND CONFIGURATIONS SHOWN ON THIS PAGE ARE TYPICAL ONLY. ADAPTATIONS MAY BE MADE AS NUMBER AND SIZES OF LOTS TO BE STORED IN BUNKER REQUIRE.
2. AN INSPECTION/INVENTORY AISLE NOT LESS THAN 18" WIDE MUST BE PROVIDED AT ONE SIDE OR END OF EACH LOT.
3. EACH LOT WITHIN THE BUNKER MUST BE ACCESSIBLE FOR MOVEMENT BY MHE. PALLET UNITS OF A SINGLE-LOT ARE CONSIDERED "ACCESSIBLE" IF NO MORE THAN TWELVE (12) "LIFTS" OF ANOTHER LOT OR LOTS HAVE TO BE MADE TO GAIN ACCESS TO THE SINGLE-LOT. A "LIFT" MAY CONSIST OF ONE (1) OR TWO (2) PALLET UNITS. PROVIDING THE CAPACITY OF THE MHE PERMITS, AND SAFE HANDLING IS NOT JEOPARDIZED.

(CONTINUED AT RIGHT)

(SPECIAL NOTES CONTINUED)

4. WHEN TWO LOTS ARE STORED ADJACENT TO EACH OTHER, THEY SHOULD BE SEPARATED BY AT LEAST 1" TO PROVIDE CLEARANCE FOR REMOVAL OF EITHER LOT.
5. A MIXED-LOT PALLET UNIT MAY HAVE FROM TWO LOTS PER PALLET UNIT UPWARDS TO AS MANY DIFFERENT LOTS AS COMPLETE ROUNDS WITHIN THAT UNIT. HOWEVER, ALL COMPLETE ROUNDS AND LOTS WITHIN THE PALLET UNIT MUST HAVE THE SAME NATIONAL STOCK NUMBER AND CONDITION CODE.
6. THE MHE AISLE MAY BE USED TO STORE ADDITIONAL LOTS, OR ADDITIONAL ITEMS THAT ARE FROM A LOT OR LOTS ADJACENT TO THE MHE AISLE, AS SHOWN IN THE AREAS ENCLOSED BY DOTTED LINES. ADEQUATE SPACE FOR MHE OPERATION MUST BE AVAILABLE FOR THE ADDITIONAL STORAGE. ALSO, COMPLIANCE WITH ALL OF THE MULTIPLE-LOT CRITERIA AS SET FORTH ON THIS PAGE MUST BE OBSERVED.