APPROVED BY	APPROVED BY
U.S. COAST GUARD	BUREAU OF EXPLOSIVES
L_ EH Fibrar	M. R. Miller
, .	SUPERVISOR, MILITARY & INTERMODAL SERVICES
DATE 5/19/80	DATE 4/30/80

LOADING AND BRACING WITH WOODEN DUNNAGE IN COMMERCIAL CONTAINERS OF PALLETIZED UNITS OF COUNTER-MEASURE FLARES (18-BOX PALLET UNIT) (WOODEN BOX)

THE DEPICTED WOODEN DUNNAGE METHOD CAN BE APPLIED TO ANY COMMERCIAL INTERMODAL 20-FOOT CONTAINER, ALTHOUGH THE DUNNAGE DIMENSIONS HAVE BEEN GIVEN FOR A 92" WIDE BY 95" HIGH (INSIDE DIMENSIONS) CONTAINER. ALTHOUGH THE LOAD AS SHOWN IS BASED ON AN 8'-6" HIGH CONTAINER, AN 8'-0" HIGH CONTAINER IS PREFERRED FOR SHIPPING THE DEPICTED LOAD. WHEN AN 8'-0" HIGH CONTAINER IS USED, THE HEIGHT OF SOME DUNNAGE ASSEMBLIES WILL HAVE TO BE LOWERED BY REMOVING SOME MATERIAL FROM THE TOP OR BOTTOM OF SOME OF THE VERTICAL PIECES.

LOADING AND BRACING SPECIFICATIONS AS DELINEATED HEREIN ARE ADEQUATE FOR SHIPMENTS TO BE MOVED BY ANY SURFACE MODE OF TRANSPORT (MOTOR, RAIL, AND WATER).


REQUIREMENTS CITED WITHIN THE BUREAU OF EXPLOSIVES PAMPHLET 6C APPLY WHEN THE SHIPMENT MOVES BY TRAILER/CONTAINER-ON-FLAT-CAR (T/COFC). SPECIAL T/COFC NOTES FOLLOW.

- A. A LOADED CONTAINER MUST BE ON A CHASSIS EQUIPPED WITH TWO BOGIE ASSEMBLIES WHEN BEING MOVED IN TOFC SERVICE.
- B. THE LOAD LIMIT OF A T/COFC RAIL CAR MUST NOT BE EXCEEDED, NOR WILL A CAR BE LOADED SO THAT THE TRUCK UNDER ONE END OF THE CAR CARRIES MORE THAN ONE-HALF OF THE LOAD LIMIT FOR THAT CAR.

DURING INTRASTATE AND/OR INTERSTATE MOVES BY MOTOR CARRIER, A PROPER CHASSIS/MODIFIED FLAT BED TRAILER MUST BE USED TO PRECLUDE VIOLATION OF ONE OR MORE "WEIGHT LAWS" APPLICABLE TO THE STATE OR STATES INVOLVED.

REVISIONS	AND MICK WRF/JES
	APPROVED, U. S. AMET ARBAMENT WATERIEL READURES COMMAND DISTURAL C. Follow
	APPROVED BY ORDER OF COMMANDING BENERAL, U. S. ARBY MATERIEL BUYELOWINEN AND READINESS COMMAND (GARCONS U.S. ARBY DEFENSE AMMANFROM CERTER AND SCHOOL U.S. ARBY DEFENSE AMMANFROM CERTER AND SCHOOL
	U. S. ARMY DARCOM DRAWING JUNE 1980
	D-SARAC-4447

DO NOT SCALE



(GENERAL NOTES CONTINUED)

- K. RECOMMENDED SEQUENTIAL LOADING PROCEDURES:
 - PREFABRICATE ONE FORWARD BLOCKING ASSEMBLY, TWO CENTER FILL ASSEMBLIES, ONE REAR BLOCKING ASSEMBLY, AND NAIL A DOOR POST VERTICAL RETAINER TO EACH DOOR POST VERTICAL, ONE RIGHT HAND AND ONE LEFT HAND.
 - 2. INSTALL FORWARD BLOCKING ASSEMBLY.
 - 3. LOAD EIGHT PALLET UNITS AND INSTALL ONE CENTER FILL ASSEMBLY.
 - 4. REPEAT STEP 3.
 - 5. INSTALL REAR BLOCKING ASSEMBLY.
 - 6. INSTALL THE TWO DOOR POST VERTICAL ASSEMBLIES (ONE RIGHT HAND AND ONE LEFT HAND).
 - INSTALL TWO DOOR SPANNER PIECES (ONE AT THE LOWEST POSITION AND ONE AT THE UPPERMOST POSITION).
 - 8. INSTALL THE SOLID FILL TYPE LOAD BLOCKING MATERIAL.
 - INSTALL THE REMAINING FOUR DOOR SPANNER PIECES STARTING WITH THE LOWEST AND WORKING UPWARD.

BILL OF MATERIAL				
LUMBER	LINEAR FEET	BOARD FEET		
1" X 4" 1" X 5" 2" X 4" 2" X 6" 4" X 4"	36 70 42 234 150	12 35 28 234 200		
NAILS	NO. REQD	POUNDS		
6d (2") 10d (3") 12d (3-1/4")	148 256 24	1 4 1/2		
DOOR POST VERTICAL RETAINER 2 REQD				

MATERIAL SPECIFICATIONS LUMBER -----:: TM 743-200-1 (DUNNAGE LUMBER) AND FED SPEC MM-L-751. NAILS -----:: FED SPEC FF-N-105; COMMON. STEEL, STRUCTURAL ----:: FED SPEC QQ-5-741; SQUARE STRUCTURAL TUBING AND HOT-ROLLED STRIP.


GENERAL NOTES


- A. THIS DOCUMENT HAS BEEN PREPARED AND ISSUED IN ACCORDANCE WITH AR 740-1, AND AUGMENTS TM 743-200-1 (CHAPTER 5).
- B. THE SPECIFIED OUTLOADING PROCEDURE IS APPLICABLE TO A LOAD OF 18-BOX PALLET UNITS OF COUNTERMEASURE FLARES PACKED IN WOODEN BOXES. SUBSEQUENT REFERENCE TO PALLET UNIT MEANS THE PALLET UNIT WITH AMMUNITION THEMS. SEE PAGE 5 FOR THE DETAIL OF THE PALLET UNIT. CAUTION: REGARDLESS OF THE QUANTITY OF UNITS TO BE SHIPPED, THE "MAXIMUM GROSS WEIGHT" OF 44,800 POUNDS MUST NOT BE EXCEEDED.
- C. THE LOAD AS SHOWN IS BASED ON A 4,700 POUND 20' LONG BY 8' WIDE BY 8'-6"
 HIGH INTERMODAL COMMERCIAL CONTAINER WITH INSIDE DIMENSIONS OF 19'-4"
 LONG BY 92" WIDE BY 95" HIGH. THE LOAD IS DESIGNED FOR TRAILER/CONTAINERON-FLAT CAR (T/COFC) SHIPMENT, HOWEVER, THE LOAD AS DESIGNED CAN ALSO
 BE MOVED BY OTHER SURFACE MODES OF TRANSPORT. NOTICE: OTHER CONTAINERS OF THE SAME DESIGN CONFIGURATION CAN BE USED.
- D. WHEN LOADING PALLET UNITS, THEY ARE TO BE POSITIONED SO AS TO ACHIEVE A TIGHT LOAD (TIGHT A GAINST THE FORWARD BLOCKING ASSEMBLY AND CONTAINER SIDEWALL). ALTHOUGH A TOTAL OF ONE AND ONE-HALF INCHES (1-1/2") OF UNBLOCKED SPACE ACROSS THE WIDTH OF A LOAD BAY IS PERMITTED, LATERAL YOIDS WITHIN THE LOAD ARE TO BE HELD TO A MINIMUM. EXCESSIVE SLACK CAN BE ELIMINATED FROM A LOAD BY LAMINATING ADDITIONAL PIECES OF APPROPRIATE THICKNESS TO THE LONGITUDINAL PIECES ON ONE OR BOTH SIDES OF THE CENTER FILL ASSEMBLIES. NAIL EACH ADDITIONAL PIECE TO THE LONGITUDINAL PIECES W/1 APPROPRIATELY SIZED NAIL EVERY 12". ADDITIONALLY, THE NUMBER AND THICKNESS OF THE LONGITUDINAL PIECES MAY BE ADJUSTED AS REQUIRED TO FACILITATE VARIANCE IN THE LENGTH OF THE PALLET UNIT. NOTE: IF THE THICKNESS OF THE LONGITUDINAL PIECES IS VARIED FROM WHAT IS DELINEATED ON PAGE 5, IT MAY BE NECESSARY TO ADJUST THE THICKNESS OF THE HOLD-DOWN PIECES TO FACILITATE PROPER HOLD-DOWN OF THE CENTER FILL ASSEMBLIES.
- E. DUNNAGE LUMBER SPECIFIED IS OF A NOMINAL SIZE. FOR EXAMPLE, 1" X 6" MATERIAL IS ACTUALLY 3/4" THICK BY 5-1/2" WIDE AND 2" X 6" MATERIAL IS ACTUALLY 1-1/2" THICK BY 5-1/2" WIDE.
- F. A STAGGERED NAILING PATTERN WILL BE USED WHEREVER POSSIBLE WHEN NAILS ARE DRIVEN INTO JOINTS OF DUNNAGE ASSEMBLIES OR WHEN LAMINATING DUNNAGE. ADDITIONALLY, THE NAILING PATTERN FOR AN UPPER PIECE OF LAMINATED DUNNAGE WILL BE ADJUSTED AS REQUIRED SO THAT A NAIL FOR THAT PIECE WILL NOT BE DRIVEN THROUGH ONTO OR RIGHT BESIDE A NAIL IN A LOWER PIECE.
- G. IN SOME CONTAINERS, SUCH AS SOME ALL STEEL CONTAINERS, THERE IS A SLOT AT THE CORNERS OF THE FORWARD WALL. A PIECE OF DUNNINGE MATERIAL MUST BE LAMINATED TO THE BUFFER PIECES ON THE FORWARD BLOCKING ASSEMBLY TO PROVIDE A FLAT SURFACE FOR THE 2" X 6" BUFFER PIECES. A PIECE OF 2" X 4", 2" X 3", OR A SPECIAL WIDTH PIECE CUT-TO-FIT CAN BE USED. THIS FILL PIECE WILL BE NAILED WITH ONE APPROPRIATELY SIZED NAILE EVERY 12". THIS PIECE IS NOT REQUIRED WHEN THE FRONT WALL OF THE CONTAINER IS SMOOTH AND FLAT.
- H. <u>CAUTION:</u> DO NOT NAIL DUNNAGE MATERIAL TO THE CONTAINER WALLS OR FLOOR, ALL NAILING WILL BE WITHIN THE DUNNAGE,
- J. PORTIONS OF THE CONTAINER DEPICTED WITHIN THIS DRAWING, SUCH AS ONE OF THE SIDEWALLS, HAVE NOT BEEN SHOWN IN THE LOAD VIEWS FOR CLARITY PURPOSES.

(CONTINUED AT LEFT)


LOAD AS SHOWN


ITEM	QUANTITY	WEIGHT (APPROX)
DUNNA GE	16	13,024 LBS 1,088 LBS 4,700 LBS
	TOTAL WEIGHT	18,812 LBS








PALLET UNIT











THE STRUT LEDGERS CAN ONLY BE PRE-NAILED TO THE DOOR POST VERTICAL ON ONE SIDE OF THE CONTAINER. THE STRUT LEDGERS ON THE OTHER SIDE ARE TO BE NAILED AFTER A LOWER DOOR SPANNER IS INSTALLED.

